PUBLIC WORKS NOTES:

- Plan and profile shall be submitted (inked mylar size 24" x 36") for all storm sewers and street projects in public right-of-ways or public easements and approved before release of site plans.
- Contractor is responsible to notify all utility companies before construction begins.
- All datum shall be based on USC and GS datum.

- The installation of improvements as required in this article shall in no case serve to bind the city to accept such improvements for the maintenance, repair or operation thereof, but such acceptance, shall be subject to the existing regulations concerning the occeptance of each type of improvement.

SHEE	TINDEX
-	TITLE
1	COVER SHEET
1	NOTES & TRAIL DETAILS
3	EXISTING CONDITIONS PLAN
4	SITE LAYOUT PLAN
	GRADING PLAN
	TRAIL PROFILES AND STORM SEWER DESIGN
7	SWM, SMP & DUTFALL NARRATIVES
7A	BIO-RETENTION SECTIONS
78	BIO-RETENTION SPECIFICATIONS
	EROSION AND SEDIMENT CONTROL NARRATIVE AND DETAIL
*	PHASE I EROSION AND SEDIMENT CONTROL /TREE PRESERVATION PLAN PAMSE II EROSION AND SEDIMENT CONTROL
1,05.	/TREE PRESERVATION PLAN
**	TREE PRESERVATION NOTES
12	TREE INVENTORY
13	SKATE AREA
14	SKATE AREA
16	GATEWAY AND SITE FURNISHINGS
16	LANDSCAPE PLAN
17	LANDSCAPE PLAN
18	LANDSCAPE PLAN AND PLANT SCHEDULE
19	LANDSCAPE NOTES & DETAILS
20	LANDSCAPE NOTES & DETAILS
21	CONSENT AGREEMENTS AND EXHIBITS

FIRE MARSHAL NOTES: N/A

All requirements relative to the City Fire Code and Virginia Building Code

PUBLIC UTILITIES NOTES:

- All water main and sanitary sewer construction shall comply with the requirements of the standard specification and plans of the Department of Public Utilities.

- All required sanitary sewer, including laterals and storm sewer shall be installed and their ditches compacted for full depth and approved by the agency having jurisdiction and all streets and easements rough graded prior to the installation of any water mains.

- The Developer shall notify the Department of Public Utilities 3 days prior to commencing construction of any water or sanitary sewer mains.
- If a private interior fire protection system is to be provided, it shall be subject to the approval of the Department of Public Utilities, Fire Marshal, and shall conform to the City plumbing code.
- 12. Working water pressure shall be N/A p.s.i.
- 13. If this property is located in a low pressure area, a booster pump may be required in the building plumbing system. If this property is located in an once where th pressure will exceed 80 p.s.i. a pressure regulating volve shall be installed by the property owner in accordance with the local plumbing code in order to eliminate water hammer and unnecessary wastage of water.
- 14. The Developer agrees to accept complete responsibility and all costs for the installation of the mains and appurtanances and for any adjustments in alignments and grade or relocations to existing mains due to the development of this property, any repairs and maintenance therefore which may be required prior to the finish grading and surfacing of the streets anyor easements and final acceptance shall not be considered or granted until offer the streets have been surfaced or the easements finally graded.

RPI MAP INFORMATION:

RPI Map No. N/A Subdivision


Lot(s) N/A

Block N/A

RCP Map No. 51-216-087

MISCELLANEOUS NOTES:

- Upon satisfactory completion of the installation of required improvemnts, as shown on the approved site plan or a section thereof, the developer shall submit to the Department of Environmental Services seven copies of an As-Built site plan cartified by the engineer, architect and/or surveyor for approvat for conformity with the approved
- The As-Built Site Plan shall be submitted and approved prior to the issuance of the
- Final approval by the Planning Commission of this site plan shall expire five years after the date of such approval if building permits have not been obtained for construction accordance therewith, unless granted by the City.
- Any proposed changes or revisions during the execution of or subsequent to implementation of the approved site plan shall be subject to City review and approval.
- The existing easement have been reviewed and determined that the proposed the site improvements are consistent with the terms of these agreements. In addition, Dominion Power and Verizon have reviewed the proposed improvements and provided consent agreements that are included on sheet 21.
- Northern Virginia Regional Park Authority (NVRPA) has reviewed this plan and is in
- No Resource Protection Area (RPA) is mapped on the site. The site is in a Resource Management Area (RMA) and is in compliance with the City's Cheeapeake Bay preserval district requirements. See site tabulation on sheet 2 for impervious cover calculations.
- 8. The site is in the Tripps Run watershed.



ARBORIST NOTES:

- All requirements relative to the City Code and City Landscaping Standards shall be complied with.
- Bonds are required for Existing Trees and new Landscaping prior to final signoff.

RECORDATION DATA:

Easement(s):

Existing easements are shown on Sheet 3. No new easements are proposed.

Subdivision(s):

Dedication(s):





APPROVALS

PLANNING COMMISSION FINAL APPROVAL:

(Date and Conditions of Approval)

On December 7, 2009, the Planning Commission approved site plan application #20090407 with a condition that staff administratively approve a resubmission that addressed the following: Additional information regarding stormwater quantity control/outfall adequacy to verify that the analysis complies with all Code requirements.

B. Inclusion of the NYRPA agreement and the most current version of all other

agreements shown on Sheet 21.

C. Information deemed by staff to meet the requirements of Section 48-1137(4) of the [City] Code (a signed statement by the owner of each property subject to the site plan indicating that the owner joins in the site plan and agrees to be bound by all site.

VARIANCES (Min detotal of Approval by BZA):

BOND(S) POSTED(Details) and Assemble):

FINAL STAFF APPROVAL:

Public Works **Public Utilities**

SUBSEQUENT ACTIONS:

AS-BUILT APPROVED (Date): __ COMMON AREA DOCUMENTS APPROVED (Date): LANDSCAPE ESCROW ACCEPTED (Date): _ CERTIFICATE OF OCCUPANCY (Date): __

Revisions Approved prior to Certificate of Occupancy: Date Approved

WEST END PARK

Name of Project 1040 West Broad Street Falls Church, Virginia

City of Falls Church, Virginia

(703) 248-5001

223 Little Falls Street, Falls Church, Virginia Patton Harris Rust & Associates

(703) 449-6700 Name of Certified Engineer or Surveyor Submitting Plan 14532 Lee Road, Chantilly, VA 20151-1679


Site Plan 8- 20090407

Sheet 1 of 21 Sheets

APPLICATION FOR REVIEW & APPROVAL BY CITY OF FALLS CHURCH, VIRGINIA

SITE PLAN TABULATIONS

87,082 S.F. (2.00 AC.) 5,600 S.F. (0.13 AC) ZONE EXISTING USE PARKVACAN' PROPOSED USE PARK BUILDING HEIGHT 45 FT. LOT COVERAGE SHPERVIOUS COVER Paved Trans Skate Area Miscellaneous concrete Pads



GENERAL NOTES

- THE PROPERTY SHOWN HEREON IS IN THE NAME OF THE CITY OF FALLS CHURCH
- 2. BOUNDARY INFORMATION SHOWN IS TAKEN FROM EXISTING CONDITIONS SURVEY PREPARED BY WALTER L. PHILIPS, INC AND DATED OCTOBER 4, 2004 AS WELL AS INSTRUMENTS OF RECORD. ALL OTHER INFORMATION SHOWN IS FROM A FIELD SURVEY PERFORMED BY PHR+A AND DATED JULY 9, 2008.
- 3. THE HORIZONTAL DATUM IS NAD 83. THE VERTICAL DATUM IS NGVD 29
- 4. TITLE IMPORMATION WAS FURNISHED BY THE CITY, DATED 5-11-2005. THEREFORE ALL ENCUMBERANCES MAY NOT BE SHOWN.
- 5. CONTOURS ARE SHOWN AT A ONE-FOOT INTERVAL
- 8M #1: ON W. &O.D. TRAIL BY EXISTING PARK ENTRANCE.:340.27
- 7. ALL CONSTRUCTION SHALL CONFORM TO THE CITY OF FALLS CHURCH VIRGINIA DEPARTMENT OF TRANSPORTATION AND/OR ADA STANDARDS AND SPECIFICATIONS,
- CONTRACTOR TO VERIFY FIELD CONDITIONS PRIOR TO AND DURING CONSTRUCTION AND NOTIFY PATTON HARRIS RUST AND ASSOCIATES AT (703)449-6700 IMMEDIATELY OF ANY DISCREPANCIES RETWEEN ACTUAL FIELD CONDITIONS AND APPROVED PLAN. SHOULD CONFLICTS BE DISCOVERED WITHIN THE INFORMATION THIS PLAN, THE CONTRACTOR SHALL CONTACT PHRAM TO DISCUSS/RESOLVE SAID CONFLICTS.
- EXISTING UNDERGROUND UTILITY INFORMATION TAKEN FROM AVAILABLE RECORDS. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE EXACT LOCATION OF ALL DUE TO THEIR FAILURE TO LOCATE AND PROTECT THESE UNDERGROUND
- 10. O DENOTES TEST HOLE REQUIRED TO DETERMINE EXACT LOCATION AND ELEVATION OF EXISTING UTILITIES. CONTRACTOR SHALL BE RESPONSIBLE FOR THE DIGGING OF TEST HOLES PRIOR TO BEGINNING OF ANY CONSTRUCTION ON THE PROJECT. IF CONFLICTS ARE DISCOVERED AS A RESULT OF TEST HOLE FINDINGS. NOTIFY PATTON HARRIS RUST AND ASSOCIATES AT (703)449-6700 IMMEDIATELY.
- 11. ALL UTILITIES ARE TO BE RELOCATED AT THE CONTRACTOR'S EXPENSE, INCLUSIVE OF ANY NECESSARY POLE RELOCATIONS
- 12. POLES ARE TO BE RELOCATED PRIOR TO CONSTRUCTION BY THE CONTRACTOR
- 13. ALL STORM SEWER SHALL REICLASS IV. LINLESS OTHERWISE NOTED
- 14. THE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE TO EXISTING ROADS AND UTILITIES WHICH OCCUR AS A RESULT OF CONSTRUCTION OF THE DEVELOPMENT COVERED BY THIS SITE PLAN, WITHIN OR CONTIGUOUS TO EXISTING RIGHT-OF-WAY.
- CONTROLLED FILLS SHALL BE COMPACTED TO 95% OF MAXIMUM DENSITY AS DETERMINED BY METHOD "A" PER STANDARD PROCTOR AASHTO T-96 , ASTM D698, OR VTM-1 AS APPLICABLE DENSITY SHALL BE CERTIFIED BY A REGISTERED PROFESSIONAL ENGINEER AND RESULTS SUBMITTED TO CITY OF FALLS CHURCH PRIOR TO PAVEMENT CONSTRUCTION. IF A GEOTECHNICAL REPORT HAS BEEN PREPARED, IT SHOULD SUPERSEDE THE REQUIREMENTS IN THIS NOTE
- 16. ALL BASE, SUBBASE AND SUBGRADE MATERIAL SHALL BE COMPACTED AT OPTIMUM MOISTURE CONTENT, WITHIN A TOLERANCE OF ± 2% OF OPTIMUA
- 17. ALL FINISHED GRADING, SEEDING, SODDING, OR PAVING SHALL BE DONE IN SUCH A MANNER AS TO PRECLUDE THE PONDING OF WATER ON THE SITE, PARTICULARLY
- 18. TYPICAL SECTIONS ARE INTENDED TO SHOW GENERAL FEATURES OF THE POSED CONSTRUCTION. FOR EXACT DETAILS AT ANY GIVEN LOCATION, SEE
- EXCAVATION SUPPORT SYSTEMS SHALL CONFORM TO THE PROVISIONS OF OSHA CONSTRUCTION STANDARD 29 CFR PART 1926 SUBPART P.
- 20. AT LOCATIONS WHERE THE FINAL SURFACE COURSE OF ASPHALT PAVEMENT IS TO BE FEATHERED INTO THE EXISTING SURFACE COURSE, THE EXISTING SURFACE COURSE IS TO BE MILLED TO A MINIMUM DEPTH OF 1" AND A TACK COAT APPLIED PRIOR TO FINAL PAVING TO INSURE A SMOOTH, WELL BONDED JOINT
- 21. THE APPROVAL OF THIS PLAN DOES NOT CONSTITUTE THE APPROVAL OF FUTURE
- 22. NO GRAVE, OBJECT OR STRUCTURE MARKING A PLACE OF BURIAL IS KNOWN TO EXIST IN THE AREAS PROPOSED TO BE DISTURBED BY THIS SITE PLAN.
- 23. WHILE THIS PLAN MAY SHOW THE APPROXIMATE RE-ALIGNMENT OF ELECTRIC, GAS, COMMUNICATIONS AND DATA LINES, DETAILED CONSTRUCTION DRAWINGS AND SPECIFICATIONS WILL BE GENERATED FOR THOSE IMPROVEMENTS BY RESPECTIVE UTILITY COMPANIES.
- 24. CONTRACTOR TO EXERCISE CAUTION DURING BLASTING OPERATIONS AND SHALL COMPLY WITH COUNTY AND STATE REQUIREMENTS AS APPLICABLE. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGES TO THE SURROUNDING PROPERTIES.
- 25. CONCRETE PAVING WITHIN THE PARK SHALL HAVE SCORING GRID PATTERN AS SHOWN ON THE PLANS. CONCRETE SHALL HAVE TOOLED JOINTS AND 2" TOOLED EDGE AT SCORE JOINTS, PER DETAIL 4 ON THIS SHEET. EXPANSION JOINTS SHALL BE LOCATED AT PERIMETER OF STRUCTURES, AND A MINIMUM OF 30'.0" OF WHERE POSSIBLE, EXPANSION JOINTS SHALL BE LOCATED TO ALIGN WITH SCORING PATTERN OR AT CHANGE IN MATERIAL

26. ALL TRAILS AND PAVED SURFACES SHALL BE ADA "ACCESSIBLE ROUTES" AND HAVE A MAXIMUM CROSS SLOPE OF 2% AND A MAXIMUM LONGITUDINAL SLOPE OF 5%. THE SLOPE OF THE SUB-GRADE MATERIAL MUST BE APPROVED BY RECREATION AND PARKS PERSONNEL PRIOR TO PROCEEDING WITH

TEMPORARY TRAFFIC CONTROL NOTES

- ALL CONSTRUCTION ACCESS ENTERING AND LEAVING THE SITE SHALL BE THROUGH THE APPROVED CONSTRUCTION ENTRANCE ONTO WEST BROAD STREET - ROUTE 7, AS SHOWN ON THE EROSION AND SEDIMENTATION CONTROL PLANS.
- NO ROAD IMPROVEMENTS ARE PROPOSED UNDER THIS PROJECT
- CONTRACTOR SHALL SCHEDULE AND COORDINATE ALL WORK REGARDING TEMPORARY TRAFFIC CONTROLS WITH THE CITY OF FALLS CHURCH.
- THE TRAFFIC CONTROL DEVICES, SUCH AS SKINING, AND OTHER SAFETY MEASURES SHALL BE IN CONFORMANCE WITH THE CURRENT VERSION OF THE
- MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES
 THE VIRGINIA DEPARTMENT OF TRANSPORTATION ROAD AND BRIDGE STANDARDS.
 THE VIRGINIA DEPARTMENT OF TRANSPORTATION ROAD AND BRIDGE
- THE VIRGINIA WORK AREA PROTECTION MANUAL
- VIRGINIA SUPPLIMENT TO THE MUTCO
- CONSTRUCTION TRAFFIC SHALL USE A FLAGMAN AT ALL TIMES WHEN LISING COMSTRUCTION THAFFIC SHALL USE A FLAGMAN AT ALL TIMES WHEN USING THE CONSTRUCTION ENTERANCE TO ENSURE PEDESTRIAN VEHICULAR TRAFFIC AND PEDESTRUM SAFETY. SHOULD TEMPORARY LANE CLOSURES BE REQUIRED. THEY SHALL BE IN CONFORMANCE WITH THE GUIDELINES FROM THE CURRENT EDITION OF THE VIRIGINIA WORK AREA PROTECTION MANUAL 2005 FROURE TICT. 81.0 (FLAGGING OPERATIONS FOR A TWO LANE ROAD) WITH
- THE EXISTING SIDEWALK SHALL BE OPEN TO PEDESTRIAN USE DURING THE CONSTRUCTION PERIOD.
- THE CONTRACTOR SHALL NOT OBSTRUCT OR CLOSE ANY TRAVEL LANE WITHOUT THE PERMISSION FROM THE CITY OF FALLS CHURCH.

SITE PLAN CONFORMANCE WITH THE WEST END PARK MASTER PLAN

IN FEBRUARY OF 2007, THE RECREATION & PARKS ADVISORY BOARD ADOPTED THE MASTER PLAN FOR WEST END PARK. THE PLAN WAS ADOPTED AFTER A SERIES OF PUBLIC HEARINGS WITH NEEDINGS OF THE PARK AND OTHER INTERESTED PARK USERS. THE ADOPTED MASTER PLAN SERVED AS THE GLIDE FOR THE DEVELOPMENT OF THE WEST END PARK SITE PLAN. THE SITE PLAN WAS PRESENTED TO, AND ENDORSED BY, THE RECREATION & PARKS ADVISORY BOARD AND THE NEIGHBORS OF THE PARK WHO ATTENDED AN APRIL 1, 2009, PUBLIC HEARING TO REVIEW THE PROPOSED SITE PLAN. COMMENTS AND SUGGESTIONS RECEIVED AT THE PUBLIC HEARING HAVE BEEN INCOMPORATION INTO THE PLAN. INCORPORATED INTO THE PLAN.

- THE WEST END PARK SITE PLAN CONFORMS TO THE MASTER PLAN FOR THE PARK. LISTED BELOW ARE SOME OF THE WAYS THE SITE PLAN MEETS OBJECTIVES OF THE MASTER PLAN:

 PRESERVES AND PROTECTS THE PARK'S NATURAL RESOURCES

 PROVIDES A VARIETY OF PASSIVE AND ACTIVE RECREATIONAL ACTIVITIES FOR ALL
- MAINTAINS THE EXISTING FACILITIES AND AMENITIES SUCH AS THE PICNIC TABLES, PLAYGROUND EQUIPMENT, BARBECUE GRELS AND WALKING TRAIL. LANDSCAPED BEDS, CONSISTENT WITH THOSE IN THE OLDER PORTIONS OF THE

- LANDSCAPED BEDS, CONSISTENT WITH THOSE IN THE OLDER PORTIONS OF THE PARK WILL BE ESTABLISHED IN THE NEW PARCEL IN THE PARK. THESE BEDS WILL FEATURE A MIX OF NATIVE SHRUSS, PERENNALS, FLOWERS AND TREES TO MIRROR THE AESTHETICS OF THE EXISTING WEST END PARK. A NEW PARK SIGN THAT WILL SERVE AS A GATEWAY TO THE PARK WILL BE INSTALLED AND AN ENTRYWAY CREATED ON BROAD STREET MAKING THE PARK VISIBLE AND RECOONLIZABLE FROM BROAD STREET. MAKING THE PARK VISIBLE AND RECOONLIZABLE FROM BROAD STREET. LANDSCAPING WILL BE INSTALLED ALONG THE WESTERN BOUNDARY OF THE PARK AND ALONG THE DICH THAT FRONTS THE PARK TO BUFFER THE PARK FROM THE NOISE AND SIGHT LINES OF THE CAR WASH AND ALONG THE PARK FROM THE OLOSSE AND SIGHT LINES OF THE CAR WASH AND ALOMOTYPE REPAIR PARKING
- LOT: A PATH WILL BE INSTALLED THAT WILL PROVIDE PEDESTRIAN ACCESS TO THE NEW SECTION OF THE PARK.
 A SKATEBOARD FEATURE WILL BE ADDED TO THE PARK.
 THE SMALL OPEN SPACE IN WILL BE MAINTAINED FOR INFORMAL DROP-IN USE.

WEST END PARK IS THE ONLY PARK OF ITS KIND IN THE CITY OF FALLS CHURCH, ITS ARBORETUM LIKE SETTING IS UNIQUE AND WITH THE SITE PLAN WILL BE PRESERVED, EVEN AS THE PARK EXPANDS AND NEW AMENITIES ARE ADDED. THE PARK PROVIDES VISITORS A QUIET, CONTEMPLATIVE SETTING, FULL OF COLOR AND NATURAL BEAUTY CREATED BY LANDSCAPE BEDS BEAMING WITH AN ASSORTMENT OF NATIVE PLANTINGS.

THE CURRENT PLAYGROUND EQUIPMENT WILL BE MAINTAINED. ENHANCEMENTS TO THE PARK WILL FOCUS ON DUPLICATING THE "GARDEN LIKE" CHARACTER OF THE OLD PORTION OF THE PARK. NEW INITIATIVES WILL IMPROVE ACCESS, ESTABLISH LANDSCAPE BUFFERS BETWEEN THE PARK AND THE BUSINESSES ADJACENT TO THE PARK AND ADD A SMALL-SCALE SKATESCARD FEATURE TO THE PARK

WEST END PARK JUSTIFICATION FOR **NO PARKING**

THE SITE PLAN FOR WEST END PARK DOES NOT INCLUDE ANY OFF STREET PARKING. THE OECISION TO NOT INCLUDE PARKING WAS A DELIBERATE ONE. IN THE CITY'S COMPREHENSIVE PLAN, WEST END PARK IS CLASSIFED AS A "NEIGHBORNOOD PARK." BY DEFINITION NEIGHBORNOOD PARKS ARE WALK ITO PARKS THAT PRIMARK! Y SERVE THE SURROUNDING NEIGHBORNOOD. THESE PARKS HAVE AMENITIES FOR PASSIVE LEISURE SOMEONNAMENT REACTION TO THE SERVICE AREA OF SUCH PARKS IS BETWEEN ATTHEST AND INFORMAL ACTIVE RECREATION BUT NOT FOR ORGANIZED SCHEDULED ATHLETIC ACTIVITIES. IN FALLS CHURCH THE SERVICE AREA OF SUCH PARKS IS BETWEEN WARTER OF A MILE AND ONE-HALF OF A MILE.


NOME OF THE PARKS IN FALLS CHURCH CLASSIFIED AS "NEIGHBORHOOD PARKS" PROVIDE OFF-STREET PARKING. SINCE THIS NEIGHBORHOOD PARK LIKE MOST IN THE CITY IS 2 ACRES OR LESS IN SZE, TAKING OPEN SPACE TO PROVIDE OFF-STREET PARKING CONFLICTS WITH THE PARKS MASTER PLANS GOAL TO PRESERVE OPEN SPACE. PARKING BRACES ALSO CREATE MORE STORM WATER RUNLOFF WHEN EVERY EFFORT IS BEING MADE TO REDUCE RUNLOFF.

IN ADDITION, PROVIDING OFF-STREET PARKING ENCOURAGES PEOPLE TO DRIVE RATHER THAN WALK OR BIKE TO WEST END PARK. THE CLOSE PROXIMITY OF THE WACOD BIKE TRAIL MAKES WEST END PARK A SITE THE CITY SHOULD MAKE EVERY EFFORT TO ENCOURAGE VISITORS TO THE PARK TO ETHER WALK OR BIKE TO THE PARK.


FINALLY, IF SOMEONE WERE TO DECIDE TO DRIVE TO THE PARK THERE IS AMPLE ON STREET PARKING ON FALLS AVENUE AND GROVE AVENUE.

2 MIN. CLEAR ZONE 2' MIN. CLEAR ZONE 3:1 MAX. GRADE BEYOND CLEAR ZONE ON BOTH SIDES OF 6'-0" for 8'-0" WHERE NOTED ON PLAN) ---- MAX. CROSS SLOPE 2% SM-2A Asphalt 21-A Stone - COMPACTED SUBGRADE


ASPHALT TRAIL TYPICAL SECTION




STONE DUST TRAIL TYPICAL SECTION



CONCRETE PAVEMENT TYPICAL SECTION (3) SCALE: N/A



TYPICAL TOOLING DETAIL FOR CONCRETE PAVING



PAVER TYPICAL SECTION

SCALE: N/A

DATE REVISTO REVISTO APRINTO DATE REVISION



WEST END PARK **IMPROVEMENTS**


CITY OF FALLS CHURCH, VA


NOTES AND TRAIL DETAILS


Patton Harris Rust & Associates, pc Engineers, Surveyors, Planners, Landscape Architects, 14532 Lee Road Chontilly, VA 20151-1679 T 703.449.6700


F 703.449.6714


	CITY PLAH # 2009040
DESIGN PHR+A	SURVEY PHR+A
DRAIN	JUNE 17, 2009
CHECKED DHS	AS SHOWN
SHEET C402NOTE 2 OF 21	FILE NO. 15907—1—0











STORM WATER MANAGEMENT NARRATIVE:

THE CONDITION OF THE EXISTING SITE IS CURRENTLY DEVELOPED AS A PARK FOR THE EASTERN PORTION OF THE SITE AND UNDEVELOPED FOR THE WESTERN PORTION OF THE SITE. THE DEVELOPED PARK AREA CONSISTS OF EXISTING GARDENS LAWN AND NATURAL AREAS, AN EXISTING STONE DUST TRAIL AND A MULCH PLAYFROUND SURFACE. THE PROPOSED IMPROVEMENTS CONSIST OF ASPHALT AND STONE DUST TRAILS, A PAVED SKATE AREA LANDSCAPING, LAWN AND OTHER OPEN NATURAL AREAS.

FOR THE 10 YEAR STORM, THE EXISTING CONDITION FOR THE SITE GENERATES AN OVERALL RATE OF FLOW OF 4.42 CFS. THE PROPOSED CONDITION RATE OF FLOW WILL BE 5.08 CFS. THIS RESULTS IN AN INCREASE OF 0.66 CFG.

STORMWATER ANALYSIS

EXISTING CONDITION:						
	AR	ža	C FACTOR	CA	INTENSITY	RATE OF FLO
	S.F.	AC.			5 MIN TC	Q 10 YR.
					IN/HR	CFS
STONE DUST TRAILS	1,730	0.04	0.50	0.02		
GRASS, GARDEN BEDS, MULCH, NATURAL AREAS	85,352	1.96	0.30	0.59		
TOTAL	87,082	2.00	0.30	0.61	7.27	4.42
PROPOSED CONDITION:						
PAVED TRAILS AND STAKE AREA	6,310	0.14	0.90	0.13		
STONE DUST TRAILS	2,690	0.06	0.50	0.03		
GRASS, GARDEN BEDS, MULCH, NATURAL AREAS	78,082	1.79	0.30	0.54		
TOTAL	87.082	2.00	0.35	0.70	7.27	5.08

ESTIMATED VOLUME PER ROUTINGS (USING POND-PACK-10):
2 YEAR VOLUME = 311° CF

"SEE POND PACK-10 VOLUME ROUTING ESTIMATIONS ON THIS SHEET FOR COMPUTATIONS

BIO-RETENTION VOLUME REQUIREMENTS

USING A 20% VOID VOLUME REMOVAL RATE IN THE SOIL MEDIA OF THE BIO RETENTION

8KO-RETENTION SURFACE AREA= 958 SF
DEPTH OF BIO-RETENTION SOIL MEDIA= 2 FT
VOLUME REMOVAL VOID RATE= 0.20

TOTAL VOLUME OF SOIL MEDIA REQUIRED TO REMOVE THE DETERTION VOLUME REQUIRED:

ACTUAL VOLUME = (958 SF) X (2 FT) X (0.20) = 383** "CF" REQUIRED VOLUME = 382 CF

**SEE BIO-RETENTION SIZING COMJUPTATIONS THIS SHEET

SINCE THE VOLUME OF SOIL MEDIA PROVIDED IN THE BIO-RETENTION AREA IS GREATER THAN THE REQUIRED SWIM VOLUME, STORM WATER MANAGEMENT REQUIREMENTS HAVE BEEN MET FOR THE 2-YR AND 10-YR STORM EVENTS

THIS STORMMATER RUNOFF LEAVES THE SITE IN AN UNCONCENTRATED, OVERLAND FLOW TO AN EXISTING DITCH THAT IS DESCRIBED IN GREATER DETAIL BELOW IN THE <u>OUTFALL NARRATIVE</u>.

BY THE ADDITION OF A BIO-RETENTION AREA TO INTERCEPT A MAJORITY OF THE IMPERVIOUS AREA STORM WATER DETENTION HAS BEEN ACHIEVED. THE VOLUME OF SOIL IS SUFFICIENT TO REMOVE THE REQUIRED VOLUME OF RINDER HOREASE FROM THE POST DEVELOPMENT BACK TO EXISTING STRIKETS.

BMP NARRATIVE:

THE PROPOSED IMPROVEMENTS RESULT IN AN OVERALL IMPERVIOUSNESS FOR THE SITE OF 9%, (7.655.5.F./187.062.5.F.). THIS IS BELOW THE CITY'S THRESHOLD OF 95% IMPERVIOUS BEFORE STORM WATER QUALITY AND ADDITIONAL POLLITION REMOVAL (BMP) IS REQUIRED. HOWEVER, THROUGH THE EXTENSIVE LANDSCAPING AND THE BLORETENTION FALLITY USED FOR STORM WATER DETENTION THAT IS PROPOSED ALONG THE SOUTHERN BOUNDARY OF THE PARK, INFORMAL STORMANTER QUALITY MEDIATION WILL BE OBTAINED. IN ACCORDANCE WITH THE VIRGINIA STORMANTER MANAGEMENT HANDED KOR FOR BMP, THE LANDSCAPE PLAN HAS BEEN DESIGNED TO TOLERATE URBAIN STRESSES AND POLITIANTS, TAXING NITO CONSIDERATION SOIL MOISTURE AND TOPOGRAPHY FOR THIS AREA. NATIVE AND WATER TOLERANT PLANT SPECIES HAVE BEEN SELECTED THAT WILL PROVIDE FLITERING AND BOLOGICAL INTERENT FOR THIS AREA. NATIVE OF NON-CONCENTRATED RIAN-OFF FROM THE SKATE, TRAIL AND OPEN PLAY AREAS. THE LANDSCAPED AREA WILL ACT AS A VEGIETIVE BUFFER BETWEEN THE SITE AREA DOWN STREAM PROPERTIES. ADDITIONALLY, THE ADJACENT DITCH WILL BE LANDSCAPED WITH NATIVE, WATER TOLERANT SPECIES TO PROVIDE ADDITIONAL BIMP MEASURES SIMILAR TO A VEGETATED SWALE.


OUTFALL NARRATIVE:


THE STORMMATER RUNOFF FROM THE SITE DRAINS OVERLAND IN A SOUTHERLY DIRECTION, DIRECTLY INTO AN EXISTING, WELL ESTABLISHED, DITCH THAT IS LOCATED IMMEDIATELY SOUTH OF, AND PARALLEL TO, THE PARKS SOUTHERN BOUNDARY. THE EXISTING DITCH IS LOCATED ON LAND OWNED BY THE MORTH-PERN VERGINAL REGIONAL PARK AUTHORITY AND DOMINION POWER. BOTH PARTIES HAVE REVIEWED THE PROPOSED BITE PLAN AND HAVE NO OBJECTION TO THE PROPOSED IMPROVEMENTS. THE FLOW IS OVERLAND AND UNCONCENTRATED WITH THE EXCEPTION OF THE FLOW (0.3 CFS) FROM A PROPOSED SODOED DITCH IN THE WESTERN PORTION OF THE SITE.

THE OVERALL DRAINAGE AREA FOR THIS DITCH IS APPROXIMATELY 9.8 ACRES AS SHOWN ON THE <u>DRAINAGE AREA MAP</u> ON THIS SHEET. FOR THE PURPOSES OF THIS OUTFALL ANALYSIS, WE HAVE DETERMINED THE 10 YEAR RATE OF FLOW TO BE APPROXIMATELY 19,95 CF. BASED ON RECENT FIELD RUN SURVEY DATA OF A TYPICAL DITCH CROSS-SECTION AND LONGITUDINAL SLOPE, WE HAVE DETERMINED THAT THE 10 YEAR WATER DEPTH IN THE DITCH ADDROXIMATELY 2.2 FIEET AND IS ADEQUATELY CONTAINED WITHIN THE BANKS OF THE DITCH. ADDITIONALLY, WE HAVE DETERMINED THAT THE 2 YEAR VELOCITY IS APPROXIMATELY 1.6 FPS, WELL BELOW MINISHIM PERMISSIBLE VELOCITY OF 2.5 FPS, AND THEREFORE, NON-EROSINE TO THE EXISTING DITCH. THE OUTCH WILL BE FURTHER STABILIZED WITH WATER TOLERANT PLANT MATERIAL TO ENHANCE EROSION PREVENTION. A TYPICAL DITCH CROSS SECTION HAS BEEN PROVIDED BELOW.

THE DITCH CONVEYS THE FLOW BY A WESTERLY DIRECTION TO AN EXISTING 24 INCH STORM SEWER THAT CROISSES WEST BROAD STREET. THE FLOW ENTERS THE EXISTING STORM SEWER THROUGH AN EXISTING CONCRETE FLARED-END SECTION. WE HAVE DETERMINED THAT THE HEADWATER DEPTH AT THE ENTRANCE OF THIS STORM SEWER IS 2.7 FEET, WITH A HEADWATER LEVATION OF APPROXIMATELY 3.9.1, WRICH MATCHES EXISTING CONDITIONS, BASED ON FEED RUN TOPOGRAPHY, THE HEADWATER WILL BE CONTAINED ON THE PRANK LAND AND NOT SPILL OVER ONTO_THE EXISTING SEDEWAY INFORMATION, THE ROAD CAPPROXIMATELY 1.7 FEET BELOW SIDEWALK ELEVATIONS, BASED ON RECENT AS-BULL FIRED SURVEY INFORMATION, THE SLOPE FOR THE EXISTING 36 INCH STORM SEWER IS 0.73%. FULL FLOW CAPACITY FOR THIS PIPE IS 194 CPS, CONSEQUENTLY, THIS PIPE WILL FLOW UNDER SURFIT HEAD PRESSURE TO CONVEY THE 193 CPS, BUT NOT MORE THAN THAT NOTED ABOVE FOR THE 10 YEAR DESIGN STORM AND APPROXIMATELY THE SAME AS EXISTING.

BASED ON THESE STATED CONDITIONS, IT IS OUR OPINION THAT THE EXISTING OUTFALL AS DESCRIBED ABOVE IS ADEQUATE FOR THE SUBJECT SITE IMPROVEMENTS.






Bio-Retention Computations

					Soil Condition												
	wates No.	(A) Draina Area		Soil Type	Fore Cow		(%F) Percent Forest	(Rv) Runoff Coef.		ed Turf	(%1) Percent Turf	(Rv) Runoff Çoef.	Impe	rvious		(Riv) Runoff Coef	(RV) Weighted Runoff Coef,
-		sí	Ac		st	Ac	*		4	Ac	*		sf	Ac	*		
X.	M.		0.696		AT THE	0.190	27%	0,05		0.397	57%	9.25		0.110	16%	0.95	0.31

1		Bio-Retention Sizing									
	(T ∀)				Depth of		(SA)		Calculated	Actum	Actual
Swele	Treatment	Design	Depth of	Depth of	Surface	Equiv.	Min Surface	Length	Width	VVIOR:	Surface Area
No	Volume	Levei	Soil Media	Gravel Layer	Storage	Storage dupth	Aree	Dio Area	Bio-Area	Bio-Ares	Provided
	cf		Ħ	ft	ft	ft	zf	Ħ	ft	ft	si .
	774		7			1.02	760	*	4.3	6.0	968
	- ,								F		



NO. DESCRIPTION DATE RENTO RENTO APRIVO DATE
REVISION

Q₂₉ = (0.4) (3.9) (9.78) = 15.26cfs



WEST END PARK IMPROVEMENTS


CITY OF FALLS CHURCH, VA

SWM, BMP & OUTFALL NARRATIVES




F 703.449.6714


	CITY PLAN / 20090407
DESIGN PHR+A	SURVEY PHR+A
DRAIM! MBR	JUNE 17, 2009
CHECKED EGV	SCALE 1" == 100'
SHEET C407SWM-DD 7 OF 21	FILE NO. 15907-1-0





BIO-RETENTION SECTION B-B

HOR. SCALE: 1"=10" VER. SCALE:1"=2"









0.40 1.25

EMERGENCY SPILLWAY CROSS-SECTION

VER. SCALE:1"=2"


BIO-RETENTION SECTION F-F HOR. SCALE: 1"=10" VER. SCALE:1"=2"

DATE REVISTO REVINTO APROVO DATE

WEST END PARK **IMPROVEMENTS**

CITY OF FALLS CHURCH, VA

BIO-RETENTION SECTIONS



Patton Harris Rust & Associates,pc Engineers, Surveyors, Planners, Landscape Architects. 14532 Lee Road Chantilly, VA 20151-1679

	CITY PLAN # 2009040
DESIGN PHR+A	SURVEY PHR+A
DRAWN	DATE
MBR	NOVEMBER 21, 2011
OHECKED	SCALE
EGV	1" = 100'
SHEET C407-A-SWM	FILE NO.
7A OF 21	15907-1-0

VIRGINIA DCR SPECIFICATION NO. 9 BIORETENTION VERSION 1.9

SECTION #: CONSTRUCTION

Construction Stage Z&S Controls. Micro-bioretention and small-scale betretention areas aboutd be failly protected by sitt feace or construction fencing, perticularly if they will rely on arithration (i.e., have no underdrains). Ideally, bioretention aboutd remain outside the limit of disturbance during construction to prevent and compaction by heavy equipment. Bioretention bests locations may be used as small sediments thaps or besists other goods ordering construction. However, these must be accompanied by notes and graphic densis on the E&S plan specifying that (1) the maximum convariant depth at the construction stage must be at least 1 foot above the post-construction installation, and (2) the facility must contain an anderdrain. The plan must also show the proper procedures for converting the temporary addinged control practice to a permanent bioretention facility, notinging dewasering, cleaned and stabilization.

The following it a typical construction sequence to properly install a bioretention basin (also see Figure 9.16). The construction sequence for micro-bioretention is more simplified. These steps many be modified to reflect different bioretention

Step 1. Construction of the bioretention area may only begin after the entire contributing dminage area has been stabilized with regression. It may be necessary to block certain carb or other inlets while the bioretention area is being constructed. The proposed site should be checked for existing utilities prior to any excavation.

Step 2. The designer and the installer should have a preconstruction meeting, checking the boundaries of the contributing compared to the constructions to ensure they conform to original design. Since other constructors may be responsible for constructing portions of the site, it is quite common to find subtle differences in site grading, dramage are private electronic that can produce hydraulically important differences for the proposed biorencation area. The designer should clearly communicate, in writing, any project changes determined during the preconstruction necting to the installer and the

Step 3. Temporary E&S controls are needed during construction of the biorestation area to divert stormwater away from the biorestation area to divert stormwater away from the biorestation area would it is completed. Special protection measures such as erceion control fabrics may be needed to protect vulnerable side object from existent during the construction process.

Step 4. Any pre-treatment cells should be excavated first and then scaled to trap sediments

Step 5. Excavators or backhoes should work from the sides to excavate the bioretention area to its appropriate design depth and dimensions. Excavating equipment should have scoops with adequate reach so they do not have to sit inside the footprint of the bioretention area. Contractors should use a cell construction approach in larger bioretention benins, whereby the besin is split into 500 to 1,000 sq. ft. temporary cells with a 10-15 foot ourth bridge in between, so that cells can be excavated from the nice.

Step 6. It may be necessary to rip the bottom soils to a depth of 6 to 12 inches to promote greater infiltration

Step 7. Place gootextile fabric on the sides of the bioretession area with a 6-inch overtap on the sides If a stone storage layer will be assod, place the appropriate depth of \$77 stone on the bottom, install the perforated underdrain pipe, pack \$477 stone to 3 inches above the underdrain pipe, pack \$477 stone to 3 inches above the underdrain pipe, and add approximately 3 inches of choices stone/pea gravel as a filter between the underdrain and the toil media layer, If no stone storage layer is used, attent with 6 inches of \$57 stone on the bottom, and

Step & Deliver the soil media from an approved vendor, and store it on an adjacent impervious area or plastic sheeting. A the media in 12-inch lifts until the decired top elevation of the binetectrion area is achieved. Wait a few days to check for settlement, and add additional randia, as seeded, to achieve the design elevation.

Step 9. Propere planting holes for any trees and shrubs, install the vegetation, and water accordingly. Install any temporary

Step 10. Place the surface cover in both cells (mulch, river stone or turt), depending on the design. If coir or jute matring will be used in lies of mulch, the matring will seed to be installed prior to planting (Step 9), and holes or slits will have to be cut in the matring on matall the plants.

Step 11. Install the plant materials as shown in the landscaping plan, and water there during weeks of no rain for the first two months.

Step 12. Conduct the final construction inspection (see Section 9.2). Then log the GPS coordinates for each bioretention facility and submit faces for entry into the local maintenance tracking database.

\$.3.Construction Impection

An example construction phase inspection checklist for Bioretention areas can be accessed at the CWP website at

http://www.cwp.org/Resource_Library/Controlling Runoff and Discherges/am, htm (scroll to Tool6: Plas Review, BMP Construction, and Maintenance Checklists)

SECTION 9: MAINTENANCE

Section 4 VAC 50-60-124 of the regulations specifies the circumstances under which a maintenance agreement to must be executed between the owner and the local program. This section sets forth inspection requirements, compliance procedures if maintenance is neglected, notification of the local program upon transfer of ownership, and right-of-entry for local program.

For bioreterrion, maintenance agreements must contain recommended maintenance tasks and a copy of an annual inspection checklist. When succe-scale bioreterrion practices are applied on private residential lots, homeoveners will need to be electated regarding factor retries maintenance needs. A dood restriction, distange causement or other mechanism enforceable by the qualifying local program must be in place to help consort that rain gardens and bioretearlion filters are maintenanced and not converted or distantbod, as well as to pass the thouseholder should be any subrequent owners. The mechanism should, if possible,

9.2. First Year Maintenance Operations

Successful establishment of bioretestion areas requires that the following tasks be undertaken in the first year following

Initial Impertions. For the first 6 months following construction, the site should be inspected at least twice after storm events that exceed 1/2 inch of rainfall.

Spot Reseasing, Inspectors should look for bare or eroding areas in the contributing drainage area or around the biometention area, and make sure they are immediately stabilized with grass cover.

Fertilization. One-time, spot fertilization may be needed for initial plantings

Watering: Watering is needed case a week during the first 2 months, and then as needed during first growing season (April-October), depending on rainful).

Remove and replace deed plants. Since up to 10% of the plant stock may die off in the first year, construction contracts should include a care and replacement warmary to ensure that repotation is properly established and survives during the first growing season following construction. The typical thresholds below which replacement is required are \$5% survival of plant material and 100% survival of trace.

9.3. Maintenance Inspections

It is highly recommended that a spring maintenance impection and cleanup be conducted at each bioretestion area. The following is a list of some of the key maintenance problems to look for:

- Check to see if 75% to 90% cover (mulch plus vegetative cover) has been achieved in the bed, and measure the depth of the
- Check for sedimens buildup at curb cuts, graved disphragens or precuncan edges that prevents flow from getting into the bed, and check for other signs of bypassing.
- Check for any winter- or salt-killed vegetation, and replace it with hardier species
- . Note presence of accumulated sand, sediment and trash in the pre-treatment cell or filter beds, and remove it.
- · Inspect bioretention side slopes and grass fifter strips for evidence of any rill or suffy erosion, and remain it · Check the bioretestion bed for evidence of mulck flotation, excessive ponding, doed plants or concentrated flows, and take
- · Check inflow points for clogging, and remove any sediment.
- . Look for any bure soil or sediment sources in the contributing drainage area, and stabilize them immediately.
- Check for clogged or slow-draining soil media, a crust forened on the top layer, mappropriate soil media, or other causes of insufficient filtering time, and restore proper filtration characteristics.

Example maintenance inspection checklists for Bioretention areas can be accessed in Appendix C of Chapter 9 of the Virginia Stormwater Management Handbook (2010) or at the Center for Watershed Protection website at:

http://www.cap.org/Rescures Library/Controlling Runoff and Discharges/an. htm.

Maintenance of bioretention areas should be integrated into routine landscape maintenance tasks. If landscaping contractors will be expected to perform maintenance, their contracts should contain specifics on unkepe bioretestain landscaping needs, such as maintaining elevation differences needed for ponding, proper mulcihing, sediment and tash removal, and limited use of fertilizers and postscides. A costomized maintenance achedule must be prepared for each bioreteration facility, since the maintenance teaks will differ depending on the tealer of bioreteration, the landscaping template chosen, and the type of surface cover. A generalized summary of common maintenance tasks and their frequency is provided in Table 9.7.

The most common non-routine maintenance problem involves standing water. If water remains on the surface for more than 48 hours after a storm, adjustments to the grading may be needed or underforms reputs may be needed. The surface of the filter bed should also be checked for accumulated sedement or a fine crust that builds up after the first everal snoom events. There are neveral sections of the filter (sty the oscient things firm, as listed below):

- Open the undordrain observation well or cleamout and pour in water to verify that the anderdrains are functioning and not clogged or otherwise in need of repair. The purpose of this check is to see if there is standing water all the way down through the soil if there is standing water on top, but not in the underdrain, then there is a clogged soil layer. If the anderdrain and stand pipe indicates standing water, then the underdrain must be clogged and will need so be scaled.
- Remove accumulated sediment and till 2 to 3 inches of sand into the upper 8 to 12 inches of soil.
- Install and wicks from 3 inches below the surface to the underdrain layer. This reduces the average concentration of fines
 in the medio bed and promotes quicker drawdown times. Sand wicks can be installed by excurvating or angering (using a
 tree mager or similar tool) down to the graved storage zone to croste vertical columns which are then filled with a clean
 open-graded coarse tend material (ASTM C-33 concrete send or similar approved and size for bioretention media). A
 sufficient number of wick drains of sufficient much be installed to meet the design deventering time for the
- · Remove and replace some or all of the soil media.

Table 9.7. Suggested Annual Maintenance Activities for Bioretention

 Mowing of grass filter strips and biorelention turf cover 	At least 4 times a year
 Spot weeding, erosion repair, trash removal, and mulch raiding 	Twice during growing seaso
 Add reinforcement planting to maintain desired the vegetation density Remove invasive plants using recommended control methods Stabilize the contributing dramage area to prevent erosion 	As needed
Spring inspection and cleanup Supplement mulch to maintain a 3 inch tayer Prune trees and shrubs	Annually
Remove sediment in pre-treatment cells and inflow points	Once every 2 to 3 years
Replace the mulch layer	Every 3 years

BIO-RETENTION FILTER AND BASIN SOIL MEDIA

A mix of natural, weshed sand meeting ASTM C-33, native soil acreemed to fine (min), and organic compost. Components shall be blanded in a pug mill (or approved equal) to create a homogenous material suitable to tito-brandfor filev., beals, and other bio-remediation facilities. The mix shall be tree of stocks, slones,

Sand: 70% - 75% Top Soil: 15% - 20%

Texture Class: Loamy Sand , Sandy loam, or Loam according to USDA texture

Typical Analysis (final product):

10% (4% min - 15% max) 5% (3% min - 9% max)

Organic Matter: 3.0% (2.5% min - 5.0% max) 6.5 (6.0 min -- 7.0 max

6.5 meg/100g (5.0 min ~ 8.0 mex) Calcium (Ca): 900 opm (800 rein - 1200 max)

100 ppm (75 min ~ 150 mex) 160 ppm (125 min ~ 225 mex) 50 ppm (40 min ~ 125 max)

WEST END PARK **IMPROVEMENTS**

CITY OF FALLS CHURCH, VA

BIO-RETENTION SPECIFICATIONS

SEE BIO-RETENTION SOIL MIX THIS SHEET FOR PREFERED SOIL MEDIA-TO BE USED

DUE TO SITE CONSTRAINTS AND THE USE OF TWO OUTFALLS:

4" UNDERDRAINS ARE USED AND WITH A MINIMUM SLOPE OF 0.50%

Patton Harris Rust & Associates,pc Engineers, Surveyors, Planners, Landscape Architects,



VAIDCR STORMWATER DESIGN SPECIFICATION NO. 9

Choking Layer

Layer

Yable 9.6. Bioretention Meterial Specifications

Alternative User inversione or pee gravel, coir and Lary a a surface Cover Learn send or sandy beam tecture.

Top Soil For Turf Cover corrected to between 6 and 77, and an 3 inch surface depth.

Che Mate in contribution

85%-88% sand
 85%-12% soil fines
 35%-58 organic master in the form of leef compost
 P-index range = 10-30, QR
 Between 7 and 21 mm².

CECs greater than 10
Use aged, shredded hardwood bark Ley a 2 to 3 inch layer on the surface of the

mulch Silter bed.
Use river stone or pea gravel, coir end Ley a 2 to 3 inch teyer of to suppress weed

Corrected to between 0 artio 1, and an organic matter content of at least 2%.

Use a non-wovan geotectile fabric with a flow rate of > 110 gal.hmin.fsq. 1 anderdrain. For hotspots and certain kent sites ordy, use an appropriate liner on bright order of the properties of the propert

(e.g., Geotex 351 or equivalent) sees only, use an appropriate siner on bottom.

Lay a 2 to 4 inch layer of send over a 2 inch layer of choker stone (typically \$6 or \$69 washed growel), which is teld over the underdrain stone.

1 inch stone should be double-weeked 12 inches for the underdrain; and clean and free of all fines (e.g., 12 to 16 inches for the stone storage layer, 17 inches for the stone storage layer, 18 needed

and clean and free of all fines (e.g., 12 to 18 Inches for the stone storage layer, if you of the properties of the stone storage layer, if you have storaged and the procession of the processi

Between 7 and 21 mg/kg of P in the soil media: The media must be procured from approved fifter media vendors.

BIORETENTION

Chantilly, VA 20151-1679

	CITY PLAN # 2009040
DESIGN PHR+A	SURVEY PHR+A
DRAWN MBR	NOVEMBER 21, 2011
CHECKED EGV	SCALE 1" = 100'
SHEET C407-B-SWM 7B OF 21	FILE NO. 15907-1-0

DATE REVS'D REWI'D APRY'D DATE



EROSION 4 SEDIMENT CONTROL NARRATIVE

PROJECT DESCRIPTION:
THIS SHITE PLAN CONSISTS OF SITE IMPROVEMENTS THAT INCLUDES THE
CONSTRUCTION OF TRAILS AND SKATE AREA. THE IMPROVEMENTS PROPOSED
HEREWITH WILL REQUIRE THE DISTURBANCE OF APPROXIMATELY 0.8 ACRES, WITHIN

THE OVERALL INTENT OF THIS PLAN IS THAT SEDIMENT AND EROSION BE CONTROLLED AT ALL TIMES DURING CONSTRUCTION, TO AT LEAST CURRENT STANDARDS OF THE VIRGINIA SEDIMENT AND EROSION CONTROL HANDBOOK AND THE CITY OF FALLS CHURCH. IT IS EXPECTED THAT, SUBJECT TO THE INSPECTORS PPROVAL, PROPOSED CONTROL MEASURES WILL NEED TO BE MOVED, MODIFIED. ADDED TO, AND/OR ELIMINATED DURING THE CONSTRUCTION PROCESS, AS NEEDED

EXISTING SITE COMOTIONS:

THIS SITE IS PRESENTLY VACANT, CONSISTING OF SCATTERED TREES AND NATIVE VEGETATION ON GENTLY ROLLING TERRAIN. AN OPEN LAWN AREA MAKES UP THE EAST PORTION OF THE SITE. THE SITE DRAINS TO AN OPEN DITCH ALONG THE

ADJACENT PROPERTY:
THE SITE IS BOUND TO THE EAST BY THE EXISTING PORTION OF THE WEST END PARK,
AND BEYOND THAT, EXISTING SINGLE FAMILY DETACHED RESIDENCES LOCATED ON
GROVE AVENUE. TO THE SOLTH, THE PARK IS BOUND BY THE WISOD TRAIL OWNED BY
THE NORHTERN VIRGINIA REGIONAL PARK AUTHORITY, COMMERCIAL
ESTABLISHMENTS, CONSISTING OF A CAR WASH AND PARKING LOT, ARE ADJACENT TO
THE PARK NORTHWEST BOUNDARY. AT THE SOUTHWEST CORNER OF THE SITE, THE
PARK HAS APPROXIMATELY 30 FEET OF FRONTAGE ONTO WEST BROAD STREET

CRITICAL AREAS: THERE ARE NO CRITICAL AREAS WITHIN THE LIMITS OF THIS SITE PLAN.

SUBLE: BASED ON GEOTECHNICAL INVESTIGATIONS, THE UPPER SOILS FOUND ON THE SITE ARE LEAN CLAYS WITH MODERATE SLOPE STABILITY AND MODERATE ERODABILITY.

EROSION & SECHMENT CONTROL MEASURES: EROSION ON THIS SITE WILL BE CONTROLLED BY RAPID STABILIZATION OF DISTURBED AREAS. ALL CUIT AND FILL SUPES SHALL BE NO STEEPER THAN 2-1. DETAILS FOR ALL EROSION AND SEDIMENT CONTROL DETAIL MEASURES ARE SHOWN ON THIS SHEET.

STRUCTURAL PRACTICES:

- TREE PROTECTION 3.38
 A FENCE BARRIER IS TO BE PLACED IN ACCORDANCE WITH THE PLAN TO PROTECT THE TREES AND OTHER VEGETATION FROM CONSTRUCTION EQUIPMENT AND SOIL COMPACTION. SUPER SILT FENCE MAY BE USED FOR TREE PROTECTION.
- 2. SUPER SET FENCE BARRIER
 SUPER SET FENCE SEDIMENT BARRIERS WILL BE INSTALLED DOWNSLOPE OF AREAS WITH GRADING TO FILTER SEDIMENT-LADEN RUNOFF FROM SHEET FLOW
- 3. TEMPORARY CONSTRUCTION ENTRANCE 3.02
 A TEMPORARY CONSTRUCTION ENTRANCE WITH A WASH RACK SHALL BE INSTALLED AT THE END OF THE PARK EXIRING MILIODY CONDITIONS, DRIVERS OF CONSTRUCTION VEHICLES SHALL BE REQUIRED TO WASH THEIR WHEELS BEFORE

VEGETATIVE PRACTICES:

1. TEMPORARY SEEDING-3.31
ALL DEPUDED AREAS WHICH WILL BE LEFT DORMANT FOR EXTENDED PERIODS OF TIME SHALL BE SEEDED WITH FAST GERMINATING TEMPORARY VEGETATION IMMEDIATELY POLLOWING GRADING, SELECTION OF THE SEED MIXTURE WILL DEPEND ON THE TIME OF YEAR IT IS A PPLIED.

MANAGEMENT STRATEGIES: SEDIMENT CONTROL PROGRAM - PHASE I

- IEP 1: 1. OBTAIN CONSTRUCTION PERMIT AND ATTEND PRE-CONSTRUCTION MEETING WITH THE INSPECTOR PRIOR TO STARTING ANY LAND DISTURBING ACTIVITIES. 2. INSTALL A STABILIZED CONSTRUCTION ENTRANCE AND ESTABLISH A PROTECTED STAGING, EQUIPMENT, AND BYDOKPILE AREAS.
- 3. CONSTRUCTION WILL BE SEQUENCED SO THAT GRADING OPERATIONS CAN BEGIN
- AND END AS QUICKLY AS POSSIBLE.

 4. INSTALL PERPHERAL MECHANICAL CONTROLS (SUPER SILT FENCE, TREE PROTECTION, AND CONSTRUCTION FENCE.)

 5. OBTAIN INSPECTIONS APPROVAL AND SIGNATURE ON PERMIT FOR SATISFACTORY COMPLETION OF STEP 1 WORK PRIOR TO PROCEEDING WITH REMAINING STE

- STEP 2:

 FRAILZE RISTALLATION OF CONSTRUCTION ENTRANCE WITH WASH RACK AS SHOWN ON PLAN, MUD AND DEBRIS SHALL BE WASHED FROM ALL CONSTRUCTION EQUIPMENT AND VENCLES BEFORE LEAVING THE SITE. THE SOURCE OF WATER SUPPLY SHALL BE A NEARLY EXISTING FIRE HYDRANT OR A WATER TRUCK. THE CONTRACTOR IS TO MAKE SURE THAT RUNGET FIRE THE CONSTRUCTION ENTRANCE IS DIRECTED TOWARDS THE EROSION AND SEDMENT CONTROLS WITHIN THE LIMITS OF DISTURBANCE.

 2. FINAL ZE INSTALLATION OF PERIMETER CONTROLS.

 3. THE CONTRACTOR SHALL KEEP THE CONTROLS AS LONG AS POSSIBLE DURING CONSTRUCTION UNTIL TO CONFICES WITH PERMANENT PROPOSED CONDITIONS, AT THAT TIME IT SHALL BE REMOVED.

SEDIMENT CONTROL PROGRAM - PHASE 2 TASK 1:

- ASK 1:

 1. THE CITY OF FALLS CHURCH INSPECTOR SHALL INSPECT ALL PHASE I CONTROLS PRIOR TO THE CONTRACTOR IMPLEMENTING CONSTRUCTION.

 2. START STORM SEWER INSTALLATION AND CONSTRUCTION.

 3. AS SOON AS THE STORM SEWER CONSTRUCTION IS FINALIZED AND ACTIVE, ADJUST THE SILT FENCE AS SHOWN ON THE PHASE II CONTROLS PLAN INSET.

- START THE GRADING, TRAIL AND SKATE AREA CONSTRUCTION AND MAKE SURE
 THAT THE ADJACENT TREES AND LANDSCAPING ARE PROTECTED FROM
- 2. AFTER CONSTRUCTION OPERATIONS HAVE ENDED AND ALL DISTURBED AREAS AFTER FINAL STABILIZED, MECHANICAL CONTROLS MAY BE REMOVED AND THE GROUND PERMANENTLY STABILIZED BY TEMPORARY SEEDING SUBJECT TO THE APPROVAL OF THE CITY OF FALLS CHURCH SITE INSPECTOR (WITHIN 30 DAYS AFTER FINAL STABILIZATION)

AFTER FINAL STABILIZATION)

- NI EMANCE PROPERINTENDENT SHALL MAKE VISUAL INSPECTION OF ALL CONTROLS AND NEWLY STABILIZED AREAS ON A DAILY BASIS, ESPECIALLY AFTER A HEAVY RAINFALL EVENT TO INSURE THAT ALL CONTROLS SHALL BE REPAIRED PRIOR TO THE END OF THE WORKDAY INCLUDING RE-SEEDING AND MULCHING, OR
- THE END OF THE INTERESTANT.

 2. SEDBRENT REMOVAL SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE AND CAUSE SEDMENTATION PROBLEMS. SEDIMENT SHALL BE DISPOSED OF BY SPREADING ON THE SITE OR HAULING

- PERILAMENT STABBLIZATION:

 1. ALL AREAS DISTURBED BY CONSTRUCTION OPERATIONS AND NEWLY GRADED
 AREAS SHALL BE VEGETATIVE AND SOLODE ON 2:1 SLOPE AND SEEDED ON ALL
 OTHER AREAS, MILCH (STRAW OR FIBER) SHALL BE USED ON RELATIVELY FLAT
 AREAS TO ALLOW SEED TO GERMINATE PROPERTY. IF SEEDING AND SOLODING
 CANNOT BE ACCOMPLISHED DURNES SCHEDULED TIME, PROTECT DISTURBED
 AREAS WITH MULCH OR JUTE MESH. RECOMMENDED SEEDING AND SOLDING TIME
 SHALL BE IN SPRING BETWEEN FEBRUARY 1 AND APRIL 30 OR IN THE FALL
 BETWEEN SEPTEMBER 1 AND OCTOBER 15.
 2. NO SEDMENT CONTROL DEVICES SHALL BE REMOVED WITHOUT APPROVAL OF
 THE CITY OF FALLS CHARCH SITE INSPECTOR.
 3. SAT FENCES SHALL BE CADE AS POSSIBLE TO THE LIMITS OF CLEARING
 AND GRADING. BRIT FENCES WILL BE CLEARED WHEN THE SIT REACHES HALF
 THE HEIGHT OF THE FENCE.
 4. THE SEEDED AREAS SHALL BE CHECKED REGULABLY TO ENSURE THAT GOOD
 STAND IS MAINTAINED. AREAS SHALL BE FERTILIZED AND RESEEDED AS NEEDED.

- AND CONSERVATION NOTES:

 NO DISTURBED AREA WHICH IS NOT ACTIVELY BEING WORKED SHALL REMAIN DEPUNDED FOR MORE THAN 7 CALENDAR DAYS UNLESS OTHERWISE AUTHORIZED
- BY THE DIRECTOR.

 2. ALL EAS CONTROL MEASURES APPROVED WITH THE PHASE I EAS CONTROL PLAN SHALL BE PLACED AS THE FRRST STEP IN GRADING.

 3. THE STORM SEWER LINE SHALL BE SEEDED AND MALCHED WITHIN 14 DAYS AFTER.

- 3. THE STORM SEWER LINE SHALL BE SEEDED AND MULCHED WITHIN 14 DAYS AFTER BACKFEL.

 4. ANY AND ALL TEMPORARY EARTH BERMES, DIVERSIONS AND SEDIMENT CONTROL DAYS SHALL BE SEEDED AND MULCHED FOR TEMPORARY VEGETATIVE COVER IMMEDIATELY (AS SOON AS POSSILE BUT NO LATER THAN 48 HR) AFTER COMPLETION OF GRADING. STRAW OR HAV MULCH IS REQUIRED. ALL SOIL STOCKPLETON OF GRADING. STRAW OR HAV MULCH IS REQUIRED. ALL SOIL STOCKPLETON, THE STORM SEWER INLET SHALL BE PROTECTED BY A SEDIMENTAMED AND MODIFIED DURING CONSTRUCTION, THE STORM SEWER INLET SHALL BE PROTECTED BY CALVERT SHALL BE PROTECTED BY CALVERT SHALL BE PROTECTED BY CALVERT INLET PROTECTION, MAINTAINED AND MODIFIED DURING CONSTRUCTION PROCESS AS REQUIRED.

 6. ANY DISTURBED AREA NOT PAVED, SOLODED OR BUILT UPON BY NOVEMBER 1, OR DISTURBED AFTER THAT DATE, SHALL BE MULCHED IMMEDIATELY WITH HAY OR STRAW MULCH AT THE RATE OF 2 TOMS/ACRE AND OVER SEEDED BY APRIL. 15.

 7. AT THE COMPLETION OF ANY PROJECT CONSTRUCTION AND PRIOR TO BOND RELASS, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ALL DENUDED AREAS SHALL BE STABILIZED.

- CONTROLLED FILL MOTES:

 1. PRIOR TO THE PLACEMENT OF ANY FILL, ALL SURFACE DRAINAGE SHOULD BE ROUTED AWAY FROM THE CONSTRUCTION AREAS.

 2. ALL FILL MATERIALS AND THE EMBARKAMENT SUBGRADE SHOULD BE APPROVED BY THE SOILS ENGRHEER PRIOR TO THE FLACEMENT OF ANY MATERIALS.

 3. FILL MATERIALS SHOULD BE PLACED IN OGREGATER THAN B IN (UNCOMPACTED) LIFTS AND COMPACTED TO AT LEAST 95% MAXIMUM AVAILABLE DRY DENSITY AS DETERMINED IN ACCORDANCE WITH SPECIFICATIONS SET FORTH IN ASTIM DOSS. THE MOSTURE CONTENT OF THE SOILS TO BE USED AS FILL SHOULD BE WITHIN 3 PERCENT, PLUS OR MINUS, OF THE OPTIMUM MOISTURE CONTENT.

DUST EMBISSION CONTROL:
THE CONTRACTOR SHALL TAKE SPECIAL CARE TO CONTROL DUST DURING THE
PROPOSED CONSTRUCTION ACTIVITIES. DUST SHALL BE ALLAYED BY MEANS OF
VEGETATIVE COVER (SEED AND MILCH IN ACCORDANCE WITH THE RECURREMENTS
PRESENTED ON THIS SHEET). ALL DISTURBED AREAS SHALL BE SPRINGLED WITH WATER AS NEEDED DURING DRY WEATHER PERIODS UNTIL A STABLE GROUND SURFACE IS ESTABLISHED. DUST CONTROL SHALL BE IN ACCORDANCE WITH THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (LATEST EDITION).

GENERAL EROSION & SEDIMENT CONTROL NOTES

ES-1: UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MANTAINED ACCORDING TO MINIMAIN STANDARDS AND SPECIFICATIONS OF THE <u>VIRCINIA EROSION AND SEDMENT CONTROL HANDBOOK</u> AND VIRGINIA REGULATIONS 4VAC50-30 EROSION AND SEDMENT CONTROL REGULATION.

ES-2: THE PLAN APPROVING AUTHORITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.

ES-3: ALL EROSKON AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING.

ES-4: A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.

ES-6: PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBBAIT A SUPPLEMENTANY EROSSION CONT

ES-6: THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES INCESSARY TO PREVENT EROSION AND SECUMENTATION AS DETERMINED BY THE PLAN APPROVING AUTHORITY.

ES-7: ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABBLIZATION IS ACHIEVED.

ES-8: DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO AN ES-9: THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES ESA: THE CONTROL ON SHALL INSPECT ALL ENCIRCH CONTROL MEASURES PERIODICALLY AND AFTER EACH RIMOFF-PRODUCING RAIMFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE MIMIEDIATELY.

PROJECT

SODDING SPECIFICATIONS

- METHODS AND MATERIALS:
 1. CLASS OF TURF GRASS SOO SHALL BE VIRGINIA STATE CERTIFIED, OR STATE APPROVED
- SUD: SHALL BE MACHINE CUT AT A UNIFORM SOIL THICKNESS OF ONE INCH, PLUS OR MINUS ONE INCH, AT TIME OF CUTTING. MEAGUREMENT FOR THICKNESS SHALL EXCLUDE TOP GROWTH AND THATCH.
- TOP GROWTH AND THATCH.

 3. STANDARD SIZE SECTIONS OF SOO SHALL BE STRONG ENOUGH TO SUPPORT THEIR OWN WEIGHT AND RETAIN THEIR SIZE AND SHAPE WHEN SUSPENDED VERTICALLY FROM A FRM GRASP ON THE UPPER 10% OF THE SECTION.

 4. INDIVIDUAL PRECES OF EOO SHALL BE CLIT TO THE SUPPLIER'S WIDTH AND LENGTH. MAXIMUM ALLOWABLE DEVATION FROM STANDARD WIDTHS AND LENGTHS SHALL BE 5%. BROKEN PADS AND TORN OR UNEVEN ENDS WILL NOT BE ACCEPTABLE.

 5. SOO SHALL NOT BE HARVESTED OR TRANSPLANTED WHEN MOISTURE CONTENT (EXCESSIVELY DRY OR WET) MAY DUVERSELY AFFECT ITS SURVIVAL.

 6. SOO SHALL BE HARVESTED, DELIVERED AND INSTALLED WITHIN A PERIOD OF 36 HOURS. SOO NOT TRANSPLANTED WHEN TRANSPLANTED WHEN SOO NOT TRANSPLANTED WHEN TRANSPLANTED WHEN TRANSPLANTED BY THE PRIOD OF 36 HOURS. SOO NOT TRANSPLANTED WITHIN THIS PERIOD SHALL BE INSPECTED FOR APPROVAL PRIOR TO ITS INSTALLATION.

BRIE PREPARATION: FERTILIZER AND LIME APPLICATION RATES SHALL BE DETERMINED BY SOILS TESTS. UNDER UNUSULAL CRICUMSTANCES WHERE THERE IS INSUFFICIENT TIME FOR A COMPLETE SOIL TEST, FERTILIZER AND LIME MATERIALS MAY BE APPLIED IN AMOUNTS SHOWN UNDER 2 AND

- PRIOR TO SODDING, THE SURFACE SHALL BE CLEARED OF ALL VEGETATION, TRASH, DEBRIS, AND OF ALL ROOTS, BRUSH, WIRE, GRADE STAKES AND OTHER TO BLECTS THAT WOULD INTERFERE WITH PLANTING, FERTILIZING OR MAINTENANCE OPERATION.

 WHERE THE SOL IS ACID OR COMPOSED OF HEAVY CLAYS, GROUND AGRICULTURAL LIMITSTOKE SHALL BE SPREAD AT THE RATE OF 100 POUNDS PER 1,000 SCUARE PEET. IN ALL SOILS THE REQUIRED LIME AND 30 POUNDS OF 5-10-5 OR EQUIVALENT FERTILIZER PER 2,000 SQUARE FEET SHALL BE UNIFORMLY APPLIED AND MIXED INTO THE TOP 3 NOHES OF SOL DURING FIRM TILLAGE OPERATIONS.

 3. SLOW RELEASE NITROGEN AT THE RATE OF 35 POUNDS PER 1,000 SQUARE FEET SHALL
- SEA PPLIED TO THE PREPARED SOIL USET PRIOR TO SO INSTALLATION. THIS MATERIAL SHALL BE APPLIED TO THE PREPARED SOIL USET PRIOR TO SOI INSTALLATION. THIS MATERIAL SHALL BE APPROXIMATELY A WALLABLE AND 29 WATER INSOLUBLE SHALL BE APPROXIMATELY AND ISOULUT LIDENE UREA (BUD) MEET THESE

- SO METALLATION:

 1. DURING PERKODS OF EXCESSIVELY HIGH TEMPERATURE, THE SOIL SHALL BE TIGHTLY RRIGATED MAMEDIATELY PRIOR TO LAYING THE SOD.

 2. THE FIRST ROW OF SOO SHALL BE LIAD IN A STRANGHT LINE WITH SUBSEQUENT ROWS PLACED PARALLEL TO AND TIGHTLY WEROGED AGAINST EACH OTHER. LATERAL JOINTS SHALL BE STAGGERED TO PROMOTE MORE UNIFORM GROWTH AND STRENGTH. MISURE THAT SOO IS NOT STRETCHED OR OVERLAPPED AND THAT ALL JOINTS ARE BUTTED TIGHT IN GROBER TO PREVENT VOICE WHICH WOULD CAUSE AIR-DRYING OF THE ROOTS.

 2. PEGGED SOD: ON SLOPING ATEAS WHERE EROSION MAY BE A PROBLEM SOO SHALL BE LAD WITH LONG EDGES PARALLEL TO THE CONTOUR AND WITH STAGGERED JOINTS SECURE THE SOO BY TAMPING AND PEGGING OR OTHER APPROXED METHODS.

 4. AS SOODING IS COMPLETED IN ANY ONE SECTION, THE ENTIRE AREA SHALL BE ROLLED OR TAMPING TO INSURE SOLID CONTACT OF ROOTS WITH SON, SURFACE, SOO SHALL BE WATERED BIMBEDATELY AFTER ROLLING OR TAMPING LINTL. THE UNDERSIDE OF THE NEW SOO PAR AND SOIL SURFACE SED SHALL BE THOROUGHLY WET. THE OPERATIONS OF LAYING, TAMPING AND RRIGATING FOR ANY PIECE OF SOO SHALL BE COMPLETED WITHIN EIGHT HOURS.

TEMPORARY SEEDING NOTES

PREPARATION

1. LIMING: AN EVALUATION SHOULD BE CONDUCTED TO DETERMINE IF LIME IS NECESSARY
FOR TEMPORARY SEEDING. IN MOST SOLS, IT TAKES UP TO 8 MONTHS FOR A PH
ADJUSTMENT TO OCCUR FOLLOWING THE APPLICATION OF LIME. THEREFORE, IT MAY BE
DIFFOLL TO JUSTPY THE COST OF LIMING A TEMPORARY SITE. ESPECIALLY WHEN THE
SOL WILL LATER BE MOVED AND REGARDED. THE FOLLOWING TABLE MAY BE USED TO
DETERMINE THE ACTUAL NEED ALONG WITH THE SUGGESTED APPLICATION RATES.

LIMING REQUIREMENTS FOR TEMPORARY SITES

RECOMMENDED APPLICATION OF AGRICULTURAL LIMESTONE 3 TONS PER ACRE

- 2 TONS PER ACRE 5.3 TO 6 2. FERTILIZER: SHALL BE APPLIED AS 600 LBS/ACRE OF 10-20-10 (14 LBS/1000 SF) OR
- EQUIVALENT NUTRIENTS. LIME AND FERTILIZER SHALL BE INCORPORATED INTO THE TOP 2 TO 4 INCHES OF SOIL IF POSSIBLE 3. SURFACE ROUGHING: IF THE AREA HAS BEEN RECENTLY LOOSENED OR DISTURBED, NO
- . SURFACE ROUGHING: IF THE AREA HAS BEEN RECENTLY LOOSENED OR DISTURBED, NO FURTHER ROUGHENNO IS REQUIRED. WHEN THE AREA IS COMPACTED, CRUSTED OR HARDENED, THE SOLID SURFACE SHALL BE LOOSENED BY DISCING, RAKING, HARROWING, OR OTHER ACCEPTABLE MEANS.

 TRACKING: TRACKING WITH BULLDOZER CLEATS IS MOST EFFECTIVE ON SANDY SOILS. THIS PRACTICE OFTEN CAUSES UNDUE COMPACTION OF THE SOIL SURFACE, ESPECALLY IN CLAYEY SOILS, AND DOES NOT AID PLAN GROWTH AS EFFECTIVELY AS OTHER METHODS OF SURFACE ROUGHENING.

SEEDING
SEED SHALL BE EVERLY APPLIED WITH A BROADCAST SEEDER, DRULL CULTIPACKER SEEDER
OR HYDROSEEDER, SMALL GRAING SHALL BE PLANTED NO MORE THAN 1 % INCHES DEEP.
SMALL SEEDS, SUCH AS KENTUCKY BLUEGRABS, SHOULD BE PLANTED NO MORE THAN %
INCH DEEP. OTHER GRASSES AND LEGUMES SHOULD BE PLANTED N TO 16 NCH DEEP.

- I. SEEDINGS MADE IN FALL FOR WINTER COVER AND DURING NOT AND DRY SUMMER
- MONTHS SHALL BE MULCHED USING STRAW MULCH.

 2. TEMPORARY SEDIMOS MADE INDER FAVORABLE SOILS AND SITE CONDITIONS DURING OPTIMUM SPRING AND FALL SECOND DATES MAY NOT REQUIRE MULCH.

AREAS WHICH FAIL TO ESTABLISH VEGETATIVE COVER ADEQUATE TO PREVENT RILL EROSION WILL BE RESEEDED AS SOON AS SUCH AREAS ARE IDENTIFIED

REFERRIG PLANT MATERIALS


THE FOLLOWING GRASS SEED MAY BE USED TO ESTABLISH TEMPORARY COVER BASED ON THE TIME OF PLANTING.

SPECIES
SO MIX OF ANNUAL RYEGRASS
(LOURM MALTELORUM) &
CEREAL (MINTER) RYE
(SECALE CEREALE)


FEB. 18 - APR. 30 ANNUAL RYEGRASS (LOLIAM MULTIFLORUM)

GERMAN MILLET (SETARIA MALICA) MAY 1 - AUG. 31

(TEMPORARY SEEDING NOTES BASED ON RECOMMENDATIONS STATED IN THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK)



STONE CONSTRUCTION ENTRANCE SCALE: N/A



EENCRYG
CHAIN 18M FENCE SHALL BE 39" ABOVE GRADE WITH 3" EMBEDDED
FOR A TOTAL FARBIC WIDTH OF 42". THE POST SHALL BE 42"
ABOVE GRADE WITH 30" PLACED BELDW GRADE (WITHOUT COMCRETE)
FOR A TOTAL LEWGIN OF 72".

- NOTES:

 1. CHAIN LINK FENCE SHALL BE FASTENED SECURELY TO FENCE POSTS WITH WHITE THES.

 2. PALTER FASHED SHALL BE FASTENED SECURELY TO CHAIN LINK FENCE WITH THES.

 3. PALTED HORIZOMTALLY 26" AT THE TOP AND MOSECURION.

 3. PALTED HORIZOMTALLY 26" AT THE TOP AND MOSECURION.

 4. WHEN TWO SECTIONS OF FASSION IS SERIED SHALL COMPONED TO THE LATEST

 4. WHEN TWO SECTIONS OF FRIEN FABRICA GAUGIN EACH OTHER, THEY SHALL
- OVERLANDED BY 6'. SE PENFORMED AS NEEDED AND MATERIALS SHALL BE REMOVED
 MAINTENANCE SHALL BE PENFORMED AS NEEDED AND MATERIALS SHALL BE REMOVED
 MAINT SEDMENT RIMED—UP REACHED BOX OF THE HOUGHT OF THE SHIPER SILT FENCE.

SUPER SILT FENCE

CONSTRUCTION FENCE

CONSTRUCTION FENCE SHALL BE EIGHT (8) FOOT HIGH CHAIN LINK FENCE SECTIONS ATTACHED TO ONE AND FIVE EIGHTS (1 5/8) INCH OUTSIDE DIAMETER STEEL PIPE WITH ELEVEN (11) GAUGE MESH IN A TWO (2) INCH DIAMOND PATTERN. THE STEEL PIPE, FENCE POST ST, SHALL BE EIGHT (8) FOOT ON CONTERS SPACING, FENCE POST CAN BE EITHER SET IN CONCRETE BLOCKS AT THE BASE OR SUNKEN INTO THE GROUND THREE (3) ADDITIONAL FOOT. FINAL LOCATIONS MAY VARY BASED WAS BEEN OF CONSTRUCTED BLOCKS AT THE BASE OR SUNKEN INTO THE GROUND THREE (3) ADDITIONAL FOOT. FINAL LOCATIONS MAY VARY BASED ON FIELD CONDITIONS AND REQUIRES CITY APPROVAL

NOTE REFER TO NOTE 3, SHEET 11 FOR TREE PROTECTION FENCE.

DATE REVS'D REWO'D APRV'S DA



WEST END PARK **IMPROVEMENTS**

CITY OF FALLS CHURCH, VA


EROSION AND SEDIMENT CONTROL NARRATIVE AND DETAILS


Patton Harris Rust & Associates,pc Engineers, Surveyors, Planners, Landscape Architects. 14532 Lee Road



Chantilly, VA 20151-1679 T 703,449,6700 F 703,449,6714

CITY PLAN # 2009040 N/A JUNE 17, 2009 SME CHECKED SCALE DHS SHEET C408ESC-NOTE FILE NO. 8 OF 21 15907-1-0





TREE PRESERVATION PROCEDURES AND SPECIFICATIONS City of Falls Church, VA - Urban Forestry / Development Services

- 1. Prior to allowing any vehicle or construction equipment to enter the site, the construction foreman and project arborist (also foreman of company doing actual tree work if different from project arborist) is to meet the City Arborust to mark the location of the limits of cleaning/ tree preservation fencing, crossion control fabric, and root pruning line (where required), access routes, storage areas, and parking areas. The location of the LIMITS OF CLEARING/TREE PRESERVATION FENCING is to be installed in accordance with the approved plas and field located from existing benchmarks, landmarks, and building stakeout survey markers. All work procedures and tree preservation measures are to be discussed at this time. An appointment must be made with the arborist for the City a minimum of three days prior to the establishment of the tree preservation measures. ree days prior to the establishment run appointment at 703-248-5183. hment of the tree preservation measures is required by City Code (Sec. 35-15 (b), see enclosed. Contact the City Arborist for an appoin
- Trees to be removed shall be clearly marked and approved by the City Arborist prior to demolition or entry of any equipment on site. A tree contractor licensed and bonded to work in the City shall perform all tree work, including all tree removals. Check with the City Arborist for a copy of the most recest

3. Tree preservation fencing shall be either of the following:

- a. Six (6) foot high chain link fence sections attached to one and five eights (15/8) inch outside diameter pipe with eleven (11) -gauge mesh in a two (2) inch diamond pattern. The fencing noted above may be temporary panels set in concrete blocks at the base and secured at the top with saddle clamps or
- b. Four (4) foot high fourteen (14) gauge welded wire fence supported by six (6) foot long metal stakes (2" width) to be spaced eight (8) feet on center and
- e-017,10.480526;Both of the fencing types noted above shall be flagged with brightly colored surveyor ribbon to improve their visibility. The contractor must maintain fencing in place throughout construction. In the event fencing must be temporarily removed for any reason, contact must be made first with the arborist at 783-248-5183. The City Arborist must grant approval before any tree preservation fencing is removed, even temporarily.
- 4. Erosion and sediment control fencing shall be placed on the inside (toward construction) from the tree preservation fencing and any root-pruning trenches. Exission control devices such as silt fencing, debris basins, and water diversion structures shall be installed to prevent siltation and/or crusion within the tree

- s. The City Arborist shall be notified a minimum of three (3) days in advance of commencing any form of tree work. Call 703-248-5183 for an appointmen
- b. Trees to be removed shall be felled so as to fall away from tree protection zones and to avoid pulling breaking of roots of trees to remain. If roots are entwined, the consultant may require first severing the major woody root mass before extracting the trees. This may be accomplished by cutting through the roots by hand, with a vibrating knife, rock saw, and narrow trencher with sharp blades, or other approved root-pruning equipment.
- c. Trees being cut within the tree preservation zone shall be cut near ground level and the stumps ground out with a walk-behind grinding machine
- d. All downed brush and trees shall be removed from the tree protection zone either by hand or with equipment sitting outside the tree protection zone. Extraction shall occur by lifting the material out, not by skidding it across the ground.
- e. Brush shall be chipped and placed in the tree protection zone to a depth of 6 inches, with no chips against the trunks of trees
- f. Structures and underground features to be removed within the tree protection zone shall use the smallest equipment possible and operate from outside the tree protection zone. The City Arborist shall be present during all such operations within the tree protection zone to monitor demolition activity. Phone 703-248-5183 at least three (3) days in advance for an appointment.
- g. Any damage to trees due to demolition activities shall be reported to the City Arborist within 6 hours so that prompt remedial action can be taken.
- h. If temporary haul or access roads must pass over the root area of trees to be retained, a roadbed of at least 10 inches of mulch shall be created to protect the soil. The roadbed material shall be replenished as necessary to maintain a 10-inch depth. The City Arborist must approve the use of any such temporary road in the tree protection area.

6. Pruning & Other Preservation Measures Specifications

- a. The City Arborist shall be notified a minimum of three (3) days in advance of commencing any form of tree work. Call 703-248-5183 for an appearance of commencing any form of tree work.
- b. Root pruning, where required, shall be mechanically done with a narrow trencher with sharp blades. Once a trench is opened up, approximately 18-24" in depth and 4" wide all exposed roots will be hand pruned so that the clean-cut ends can regrow.

The tree preservation fencing shall be placed 6-12* outside the root-pruning trench (construction side of the trench). The crossion and sediment fencing shall be placed outside the tree preservation fencing (construction side of the fence).

Where required, apply a slow-release complete fertilizer containing major and trace elements, but low in water-soluble mitrogen during the season before the commencement of construction. An application of a mychorrizae product may also be required to assist in the preservation of highly stressed trees.

- c. All trees to be saved will be pruned (in accordance with American National Standards Institute (ANSI) Standard Practices for Trees, Shrubs, and Other Woody Plan Maintenance ANSI A300 and adhere to the most recent edition of ANSI Z133.1.
- d. Treat any disease or insect pest as required to reduce stress on trees
- ve all invasive vines growing on trees and from the area around the tree
- f. Specifications for work to be performed on individual trees shall be indicated under the "maintenance" column of the Tree Survey.
- g. All trees within the project area shall be pruned to:
 - Clear the crown of diseased, crossing, weak, and dead wood to a minimum size of 1 ½ inches diameter; provide 14 feet of vertical clearance over streets and 8 feet over sidewalks; remove stude, cutting outside the woundwood fissue that has formed around the branch; reduce end weight on heavy, horizontal branches selectively removing small diameter branches, no greater than 2 to 3 inches near the ends of the
- h. Where temporary clearance is needed for access, branches shall be tied back to hold them out of the clearance zone. The City Arborist must approve such i. Pruning skall not be performed during periods of flight of adult boring insects because fresh wound attract pests. Pruning shall be performed only when the
- i. All work must be performed by a tree contractor licensed and bonded to work in the City and in accordance with the direction of the project certified arborist and the City Arborist
- k. Interior branches shall not be stripped out.
- 1. Pruning cuts larger than 4 inches in diameter, except for dead wood, shall be avoided.
- m. Pruning cuts that expose heartwood shall be avoided whenever possible
- n. No more than 20 percent of live foliage shall be removed from a tree at on time.
- o. While in the tree, the arborist shall perform an aerial inspection to identify defects that require treatment. Any addition work needed shall be reported to the

TREE PRESERVATION PROCEDURES AND SPECIFICATIONS CONTINUED City of Falls Church, VA - Urban Forestry / Development Services

- p. Brush shall be chipped and chips shall be spread underneath trees within the tree protection zone to a maximum depth of 6 inches, leaving the trunk and root flare clear of chips.
- q. It may also be necessary to fertilize, serate and otherwise treat the "trees to be saved" as required by the arborist for the City, following a meeting with the waer's/developer's arborist and approval of the "tree preservation plan". All tree work must be completed prior to construction
- r. 'Selective clearing' in wooded areas will be allowed only under the direction of the City Arborist. Trees to be removed will be felled by hand so that minimal damage is done to "trees to be saved".
- s. No vehicles or storage of materials of any kind will be allowed inside the limits of clearing. No storage of material or debris will be allowed within the "tree save area". No burning will be allowed on site.

7. Construction Specification

- Supplemental water shall be supplied to trees being preserved when natural rainfall is less than 1° a week, from early spring until the ground freezes in the fall. Irrigation should be designed to wet the soil to a depth of 2-3 feet. Lacking a source of water early on the construction site, this may be accomplished by constructing a 6° berm around the tree protection zone and filling the basin with a water track or by injecting the soil using a pressure system from a truck mounted water tank. Shallow frequent watering should be avoided.
- b. Have a licensed and bonded tree contractor remove torn, hazardous, or prominent deadwood as it occurs, using ANSI standards noted under # 4 above
- c. Where construction traffic must occur in the area of tree roots it shall be necessary to apply the following procedure: cover undisturbed soil with 10-15 inches wood chips and topped with chain link fence pulled taught and anchored or topped with 5/8 to 3/4 inch plywood with non-skid surface.
- d. Where compection occurs during construction, vertical mulch with good quality compost.
- e. Before grading, pad preparation, or excavation for foundations, footings, walls, or trenching, relevant trees shall be root pruned 1 foot outside the tree protection zone by cutting all roots cleanly to a depth of 24 inches to the maximum depth of root penetration, (usually 3 feet). Roots shall be cut by manually digging a trench and cutting exposed roots with a saw, vibrating knife, rock saw, narrow trencher with sharp blades, or other approved. ing conjument. Pruned roots shall be promptly covered with soil
- f. Any roots demaged during grading or construction shall be exposed to sound tissue and cut leanly with a saw and promptly covered with moist soil.
- g. Soil from trenches, basements or other excavations shall not be placed within the tree protection zone, either temporarily or permanently. Soil stockpiles should be placed only in previously designated areas. No vehicles or construction equipment shall be parked in the tree protection zone.
- h. No burn piles or debris pits shall be placed within the tree protection zone. No ashes, debris or garbage may be damped or buried within the tree protection zone. No materials of any kind shall be stored in the tree protection zone.
- i. Maintain fire-safe areas around fenced areas. Also, no heat sources, flames, ignition sources, or smoking is allowed near mulch of trees
- j. A copy of the "approved plan" and TREE PRESERVATION PROCEDURES AND SPECIFICATIONS must be maintained on site at all times.
- k. All underground utilities and drain or irrigation lines shall be routed outside the tree protection zone. If lines must traverse the protection area, they shall be anneled or bored under the tree(s) with the approval of the City Arborist.
- 1. A licensed and bonded tree contractor must perform additional tree pruning required for clearance during construction under the direction of the City Arborist. Construction workers shall not be allowed to prune trees.
- m. Any herbicides placed under paving materials must be safe for use around trees and labeled for that use. Any pesticides used on site must be tree-safe and
- n. If injury should occur to any tree during construction, it should be treated as soon as possible under the direction of the City Arborist
- o. The City Arborist must monitor any grading, construction, demolition, or other work that is expected to encounter tree roots
- p. At the completion of construction (and all equipment has been removed from site), notify the City Arborist for an inspection before removing the tree preservation fencing. At this time, all trees will be inspected and any repairs needed will be stipulated by the City and promptly made by the Contractor. (Refer to Sec. 35-15(h) of the City Code for guidance on finalizing the requirements of the bond agreement.
- 8. The planting of the new tree(s) specified on the plan shall take place after the completion of construction. The City Arborist must inspect the trees prior to planting (see Arborist Notification) and also inspect the placement and installation of the tree(s). All products and workmanship related to the planting of the tree(s) must be in secondance with the Tree Planting Specifications statched. The Contractor(O-contract City with a copy of a one-year guarantee from the landscape contractor for the newly planted tree(s). The tree will need to be thriving and in good condition one year from the date of
- e-017;e-017;i0.480909;If you have questions on any of the "procedures" or "specifications" noted above or concerns that may arise during construction, please contact the City Arborist at (703) 248-5183 or the Senior Urban Forester at (703) 248-5016.

ARBORIST NOTIFICATION:

THE CITY OF FALLS CHURCH ARBORIST MUST BE NOTIFIED A MINIMUM OF THREE (3) DAYS PRIOR TO REMOVAL, PRUNING, OR PLANTING OF ANY TREES OR PLANT MATERIAL. THE PROPOSED PLANT MATERIAL IS TO BE INSPECTED PRIOR TO PLANTING BY THE CITY ARBORIST AND PROJECT'S LANDSCAPE ARCHITECT. PLANTS THAT HAVE NOT BEEN INSPECTED BY THE CITY ARBORIST SHALL BE REDICTED. TO ARRANGE AN APPOINTMENT CALL (78) 244–3133.

NOTE: The general contractor is responsible for stockpiling all toptoil acquired in any site excavation of hardscape features such as walks, curbs, etc. Finish grading around these curbs, walks and plant berk at building foundations will be brought to within. J of one foot of the grades shown on the civil engineering plan. The owner/hardscape contractor is responsible for all fluish grading within 0 - 1. of a foot site architecture, and the final hardscape; installation.

TREE REMOVAL AND PRESERVATION NOTES City of Fails Church, VA - Urban Forestry / Developin

	***************************************			West End Park Improveme		
Ol see	Botanical Name	Common Name	Size (dish)	Preservation Measure	Save/Remove	Commer
					<u> </u>	<u> </u>
4	Querous alba	White oak	35	install pethwey by hand throughout	SAVE	
5	Quercus albs	White oak	25	dripline of true; install TPF	SAVE	ļ
3	Quercus ansa	TAINING CAME	+ - zo -	install pathway by hand throughout driptins of tree; install TPF	SAVE	
167	Morus alba	White mulberry	19/16/7/7	HODS	REMOVE	within LC
169	Mona albe	White mulberry	4	install TPF	SAVE	appears co o
170	Morus albe	White mulberry	4	install TPF	SAVE	appears co o
171 172	Morus alba Morus alba	White mulberry White mulberry	12	install TPF	SAVE	appears co o
173	Morus alba	White mulberry	5	Install TPF	SAVE	appears co o
174	llex x attenueta "Fosteri"	Foster's holly	5	install TPF	SAVE	1
175	Quercus pakustris	Pin oak	15	instali TPF	SAVE	
176	Acer plantanuides	Norway maple	11/11/12/11	none install TPF	REMÓVE	highly inva
178	Quercus sibe Prunus seroline	White dek Black dherry	14//	none	REMOVE	
179	Prunus serolina	Black cherry	14/13	none	REMOVE	
180	Acer plantanoides	Norwey maple	4/5	no longer exists	REMOVED	
181	Quercus albe	White oak	39	install TPF	SAVE	
182	Acer plantanoides	Norway maple	11	no longer exists	REMOVED	ļ
184	Acer Prenus	Norway maple Black cherry	11	no longer exists no longer exists	REMOVED	
186	Acer plantenoides	Norway maple	6	none	REMOVE	highly bye
186	fire opeca	American holly	15/9/7/7	install TPF	SAVE	
187 186	Prunus serotina	Black cherry	5	install TPF	SAVE	
188	Prunus serotina Prunus serotina	Black cherry Black cherry	9	1000	REMOVE	
190	Quercus pakistris	Pin oak	5	instal TPF	SAVE	
191	Prunus serotina	Black cherry	10	none	REMOVE	
192	Quercus pakustris	Pin dak	5	install TPF	SAVE	İ
193	Ulmus americana	American etm	13	install TPF	SAVE	
197	Нех ораса	American holly	19 23	install TPF	SAVE	
196	Robinia pseudoscacia Robinia pseudoscacia	Black locust Black locust	15	instell TPF instell TPF	REMOVE REMOVE	
333	Prumos serolima	Black charry	4/5	RISKOBI (PF	REMOVE	LOC - phas
334	Aoer plantanoides	Norway maple	12	none	REMOVE	highly inve
335	Acer plantanoides	Norway maple	1 1/3	ROTH	REMOVE	highly inve
35.01	Prunus serotins	Black cherry	15	none	REMOVE	highly inva
336	Ulmus americana	American elm	14	none	REMOVE	LOC - phes
337	Prunus serotina	Black cherry	5	none	REMOVE	LOC - phas
338 339	Prunus serotine not on plan	Black cherry	15/15/15	INSISH TPF REMOVE FROM PRE LIMINARY TRE	SAVE	ֈ
340	Prunus sorotina	Black cherry	12	none	REMOVE	within LC
341	Prunus serotina	Black cherry	14	none	REMOVE	within LC
342	Prunus serotina	Black cherry	4/5	none	REMOVE	LOC - phase
343	Acer plantanoides	Norway maple	5	none	REMOVE	highly inva
344	Acer plantanoides	Nonway maple	4	none	REMOVE	highly inva
345 346	Robinia pseudoacacia Robinia pseudoacacia	Black locust Black locust	10/14	install TPF	SAVE SAVE	
347	Robinia pseudoacacia	Black locust	14	install TPF	SAVE	
348	Robinia pseudoscacia	Black locust	13	install TPF	SAVE	
349	Acer plantanoides	Norway maple	3	none	REMOVE	within LC
350	Acer plantanoides	Norway mapte	4	norse	REMOVE	within LC
351 352	Acer negundo Julgens nigre	box ekter Black walnut	4/5	none	REMOVE	within LC within LC
363	Julgans nigra Julgans nigra	Black walnut	4	none	REMOVE	within LC
354	Prunus serotina	Black cherry	3	none	REMOVE	within LC
355	Julgans riigra	Black walnut	10	none	REMOVE	within LC
358	Pholinia Ireaeri	Photinia	r	install TPF	SAVE	adjust LO
357 358	no longer exists	REMOVE REMOVE	 		 	ļ
58.01	no longer exists Arbovitos	White coder	6	install TPF	SAVE	adjust LO
58.02	Arborvilae	White ceder	6	install TPF	SAVE	adjust LO
58.03	Arborvitee	White cedar	6'	install TPF	SAVE	adjust LO
359	Robinia pseudoacacia	Black locust	14	install TPF	SAVE	
360	Diospyros virginians	Persimmon	3	none	REMOVE	
361 362	Robinia paeudoaceicia unknown species	Black locust dead	15	install TPF	REMOVE	ļ
363	Prunus serotina	Black cherry	12/6/10	none install TPF	SAVE	
364	Prunus serotina	Black cherry	5	name in	REMOVE	
365	Robinia pseudoacaola	Steck locust	17/17	install TPF	SAVE	1
366	Robinia pseudoacacia	Black locust	10	Install TPF	SAVE	
		Black cherry	4	none	REMOVE	1
367	Prunus serotine					
	Prunus serotina Prunus serotina Prunus serotina	Black cherry Black cherry	3 3	none	REMOVE REMOVE	

07.01.09 Jill-Anne Spence ISA Certified Arborist MA-3203em

LOC limits of clearing and grading

THIS SHEET FOR TREE PROTECTION ONLY

DATE NEWS'D NEWY'D APRIV'D DATE



WEST END PARK **IMPROVEMENTS**

CITY OF FALLS CHURCH, VA

TREE PRESERVATION NOTES

Patton Harris Rust & Associates,pc Engineers, Surveyors, Planners, Landscape Architects,

14532 Lee Road Chantily, VA 20151-1679 T 703.449.6700 F 703,449,6714

	CITY PLAN # 20090407
DESIGN PHR+A	SURVEY PHR+A
DRAWN SME	JUNE 17, 2009
CHECKED DHS	SCALE N/A
SHEET C411TP 11 OF 21	FILE NO. 15907-1-0

TREE PRESERVATION INVENTORY NOTE:

CONTRACTOR SHALL REFER TO SHEETS 9&10, THE EROSION AND SEDIMENT CONTROL/TREE PRESERVATION PLAN, AND SHEET 11, TREE PRESERVATION NOTES FOR REMOVAL AND PRESERVATION. THE INVENTORY PROVIDED ON THIS SHEET SHALL IS PROVIDED AS INFORMATION ONLY AND SHALL NOT BE USED BY THE CONTRACTOR FOR TREE REMOVAL AND PRESERVATION.


Appendix
The Inventory
West End View Park
City of Falls Church, Virginia
February 24, 2009

Prepared by
Bdward P. Millbous
TresePleased*
ASCA RCA #350 ISA #MA-0004A MD TE #458

Irea #	Hattoe	Size	Condi	on Comment	Becommendation
4	white oak	34	.75		
	Overcus alba Species Rating: RULE: 51-100	95%		This tree would be desirable in a new setting, Dead branches in this tree's crown are a minor problem.	
5	white oak Guercus aiba Species Rating; RULE: 61-100	25 95%	.75	This tree would be desirable in a new setting. Dead branches in this tree's crown are a minor problem.	
167	white mulberry Morue albe Species Rating: RULE: 26-50	19/16/7/ 30%	7 .69	One of the worst invasive exotics, it is an undestrable tre Included bark is evident. Also tagged #188	c.
169	white mulberry Morus alba Species Rating: RULE: 6-10	30%	.75	One of the worst invasive excelce, it is an undesirable tre	9.
170	white multierry Morus alba Species Rating: RULE: 6-10	30%	.75	One of the worst investive exosics, it is an undestrable tre This true leans excessively.	9.
171	white mulberry Morus alba Species Rating: RULE: 6-10	30%	,76	One of the worst investive exotics, it is an undesirable tra	6.
172	white mulberry Moras alba Species Rating. RULE: 6-10	12 30%	.75	One of the worst investive ecosics, if is an undesirable tre	
173	white mulberry Morus albe Species Rating: RULE: 6-10	5 30%	.75	One of the worst invasive existics, it is an undeckable tre	¢.
174	Foster's holly Hex x attenuata 'For Species Rating: RULE: 26-50		.75		
175	pin oak Cuercus palustris Species Rating: RULE: 26-50	15 70%	.75	Bark was damaged near the bade of the tree years ago.	
176	Norway maple 1 Aper platanoides Species Rating: RULE: 6-10		11 .66	Nonway maple is a popular but invasive exotic species. This tree crowds a better tree. English ky is attached to this tree's bunk.	
177	white oak Guercus alba Species Rating: 9 RULE: 51-100	14/7	.76	Assorted viries are attached to this tree's trunk. This tree is crowded.	
	black cherry Prunus serosine Spacies Rating: 6 RULE: 6-10	5	.60	Ris tree lears excessively. This tree crowds a better tree.	
	otack cherry Prunus serotine Species Rating: 6 RULE: 11-25	14/13	.72	inglish iny is allached to this tree's trunk. Tils tree crowds a better tree.	
	ehite osk Overcus alba Species Rating: 9 RULE: 11-25	30 5%		Sead branches in this tree's crown are a minor problem. There is spurse growth in this tree. his tree is crowded.	Clean of wood 1.5" or larger. A treatment of pachlobultrazol may reinvigorate this tree.
	forway maple Acer platenoides Species Rating: 4 RULE: 1-5	6 5%	.75	lorway maple is a popular but invasive exotic species. his troe crowds a better tree.	
	American holly liex opeca Species Rating: 8 RULE: 51-100		.72	natuded berk is evident.	
	Nack cherry Prurus seretrus Species Rating: 6 BULE: 11-25	5	.75	his tree is crowded.	
	Heck cherry Prurius seroline Species Rating: 6 RULE: 6-10	7 0%	.69	his tree leans excessively. his tree la crowded.	

Irea f				ion Comment	Becommendation
189	black cherry Prunus serotina Species Rating:	9 80%	.75	This tree is crowded.	
	AULE: 11-25				
190	pin oak Quercus pakistris Species fissing:	5 70%	.75	Tris tree is crowded.	
191	RULE: 26-50 black oherry	10	.89	This tree leans excessively.	
	Prunus serotina Species Hating: RULE: 11-25		.03	This tree is crowded. Assorted vines are stanched to this tree's trusk.	
192	pin cek	5	.75	Assorted vines are attached to this tree's trunk.	
	Querous palustris Species Rating: RULE: 26-50	70%			
193	American olm Ulmus americana	13	.75	Obscured hazard: This tree's trunk is hidden from view. Assorted vines are attacted to this tree's trunk. Dutch elm disease is a threat to any American elm.	Clear away obstructions so observations can be me
	Species Reting: RULE: 11-25	35%		COLIC MOTO LUMBERS OF RESPONDED COMP.	
197	American holly	19	.75	This is a platitate (female) tree. Vandalized: initials carved into trunk.	
	Rex opace Species Rating: RULE: 26-50	85%		THE SCHOOL SHEEKS CONTROL ETG. SUPPL.	
198	black locuet	23	.75	Stack locusts are olusy when small, but are not long-lived.	Prune out black cherry at its base.
	Robinia pseudoecac Species Rating: RULE: 11-25				
199	black locust	15	.76	Obscured hazard: This tree's trunk is hidden from view. Assorted vines are attached to this tree's trunk.	Clear away obstructions so observations can be me
	Robinia pseudoacad Species Rating: RULE: 11-25			NOON MAD AN AD OLD WITHOUT MIT HIM TO BE TO THE TOTAL	
333	black ofterry	4/5	.5	There is apparate growth in this tree. This tree is auppressed (dominated) by a larger tree.	Do not save this tree remove it when clearing.
	Prunus aerotina Species Rating: RULE: 26-50	80%		Trio in the temper of the contraction of the seasons of the season	
334	Norway maple	12	.66	Norway maple is a popular but investive exotic species. It appears this tree was uproofed a number of years ago.	Do not save this tree remove it when clearing.
	Acer platanoides Species Plating: RULE: 1-5	45%		a approach the east was approved a facilities of years ago.	
335	Nonway maple	4/3	.75	Norway maple is a popular but invasive exotic species.	
	Acer platencides Species Rating: RULE: 28-50	15%			
335.01	black charry Prunus serosing	15	.63	It appears this tree was uprooted a number of years ago, near tree #335	
	Species Rating: 6 RULE: 1-5	30%			
336	American sim: Ulmus americana Species Rating:	14	.75	Assorted wines are attached to this tree's trunk. Dusch elm disease to a threat to any American elm.	
337	RULE: 11-25 black charry		.75		
 ,	Prunus serceina Species Rating:		./3		
338	RULE: 28-50 black cherry	15/15/1	15 .69	Obscured hazard: This tree's trunk is hidden from view.	Clear away obstructions so observations can be ma
	Prunus serotina Species Rating: 6 RULE: 11-25			Obscured hazard: This trea's srunk is hidden from view. Assorted vines are attached to this tree's trunk.	and one of the state of the sta
	black cherry	12	.76	Obscured hazard: This tree's trunk is hidden from view. Assorted vines are attached to this tree's trunk.	Clear away obstructions so observations can be made
	Prunus serotine Species Rating: 6 RULE: 26-50	0%		ADDICTION THROUGH BY BRIBLINGS BY HAS DEED BY BYTHE.	
	black cherry Prunus serolina	14	.76	Obscured hazard. This tree's trunk is hidden from view. Assorted vines are attached to this tree's trunk.	Clear away obstructions so observations can be made
	Species Rating: 6 RULE: 26-50	0%			
	black cherry	4/7	.80	Assorted vines are attached to this tree's trunk. This tree lears excessively.	
	Prunter serotina Species Rating; 6 RULE: 11-25	0%		·····	
	Norway maple	5	.59	Nonway maple is a popular but invasive exotic species. Bank has been demaged near the base of the free.	
	Acer platanoides Species Rating: 4 RULE: 1-5	5%		The book damaged had the being of the first.	
	Norway maple Acer pletanoides Species Rating: 4 RULE: 1-5	4 5%	.66	Norway maple is a populer but invasive excels species. Borar damage is evident.	The second secon
345	black locust	17	.75	Black locusts are okey when small, but are not long-lived.	
	Robinia pseudosceci Species Rating: 5 RULE: 11-25	8			
	black locust	10/14	.63	Black locusts are okay when small, but are not long-lived. Obscured hazard: This insets trunk is hidden from view.	Clear away obstructions so observations can be med
	Robinia pseudososcii Species Rating: 6			Obsoured hazard: This triefs trunk is hidden from view. Assorbed vines are attached to this free's trunk. One leader is dead.	Prime out the dead leader.

===					
347	black locust Hobinia perudoeca Species Rating: RULE: 11-25		.75	Obsoured hazard: This tree's trunk is hidden from view. English ky is attached to this tree's trunk. Black locusts are oldly when small, but are not long-lived.	Clear away obstructions so observations can be made.
348	black locust Robinia pseudosca: Species Rating: RULE: 6-10		.5	Obscured hazard: This tree's trunk is hidden from view. English ky is attached to this tree's trunk. Improperly pruned: this time was topped years ago. Black locusts are oldey when small, but are not long-kved.	Clear away obstructions so observations can be made.
349	Norway maple Acer platanoides Species Rating: RULE: 11-25	3	.75	Norway maple is a popular but invasive excec species.	
350	Norway maple Acer pletenoides Species Reting: RULE: 11-25	45%	.75	Norwey maple is a popular but invasive exotic species.	
\$61	boxetder Acer negundo Species Bating: : FULE: 11-25	4/5 35%	.69	Fernals trees harbor boxelder bugs, a nuisance pest. This is a pietiliste (fernale) tree. This tree leans excessively.	Do not save this tree remove it when clearing.
152	black walnut Jugiens nigra Species Rating: I RULE: 26-50	7	.75	Assorted vines are attached to this true's trunk.	
153	black wainut Jugisins nignz Species Rating: t RULE: 11-25	4	.66	This tree has a poor form.	
15-4	black cherry Prunus aerotina Spacies Rating: t RULE: 28-50	3	.75		
155	black walnut Jugians nigra Species Rating: 8 RULE; 51-100	10	.75		
59	bisck locust Robinia pseudoscac Species Rating: 9 RULE: 11-25		.75	Obscured hazard: This tree's trunk is hidden from view. Assorted vines are attached to this tree's trunk. Black locusts are okey when small, but are not long-lived.	Clear away obstructions so observations can be made.
80	persimmon Diospyros virginiana Species Rating: E RULE: 51-100	3	.75	This tree would be desirable in a new setting. This tree has no chance of surviving construction.	Do not save this tree remove it when clearing.
61	black locust Robinia pseudoacaca Species Rating: 5 RULE: 11-25		.75	Obscured hazard: This tree's trunk is hidden from view. Assorted vines are attached to this tree's trunk. Black locuste are okay when amalt, but are not long-lived.	Clear away obstructions so observations can be made.
62	unidentified RULE: 0	4	o	This tree is dead.	
63	black focust Robinia pseudoscaci Species Rating: 5 RULE: 6-10		.66	Obscured hezard: This tree's trunk is hidden from view. Assoned vines are attached to this tree's trunk. Black locusts are olday when small, but are not long-lived.	
84	black cherry Prunus serrotina Species Rating: 6 RULE: 11-25	5	.75	This tree would be desirable in a new setting. This tree has no chance of surviving construction.	Do not save this tree remove it when clearing.
66	black locust Pobinia pseudoscaci Species Rating: 5 RULE: 11-25		.99	Obscured hazard. This tree's trunk is hidden from view. Assorted vines are attached to this tree's frunk. Black locuets are okay when small, but are not long-fived.	Clear away obstructions so observations can be made.
66	black locust Robinia pseudoacuca Species Rating: 5 RULE: 11-25		.75	Assorted vines are attached to this tree'e trunk. Black locusts are okay when small, but are not long-éved.	
67	black cherry Prunus serolina Species Rating: 6 RULE: 11-25	4	.76		
68	black charry Prunue serotina Species Rating: 6 RULE: 6-10			This tree has a poor form.	
60	black cherry Prunus serotins Species Rating: 6 RULE: 6-10			This tree has a poor form. This tree has no chance of surviving construction.	
	Photinia			e rating 57	
56	Photnia spp. Species Rating 66 Rule 11-25	17" ht. 5%	.75	Stand of three photinias.	Save these Tree,
58.01	Arborvitale Thuje spp. Species Rating 75 Rule 11-25	12° ht. %	.55	This tree is crowded but worthy for screening.	Save this Tree.
58.02	Arborvitae Thujs spp. Species Reting 75 Rule 11-25	147NL 5%	.75		Save this Tree.
58.03	Arborvitae Thuje app. Species Rating 75 Rule 11-25	157nt.	.75		Save this Tree.





WEST END PARK IMPROVEMENTS

CITY OF FALLS CHURCH, VA

TREE INVENTORY

Patton Harris Rust & Associates,pc Engineers. Surveyors. Planners. Landscape Architects.



14532 Lee Road Chantilly, VA 20151~1679 T 703.449.6700 F 703.449.6714


	CITY PLAN € 20090407
DESIGN	SURVEY
PHR+A	PHR+A
DRAWN	DATE
SME	JUNE 17, 2009
CHECKED	SCALE
DHS	N/A
SHEET C412TP	FILE NO.
12 OF 21	15907-1-0

SKATEABLE ELEMENTS NARRATIVE

THREE (3) PRE-CAST CONCRETE ELEMENTS ARE PROPOSED WITHIN THE SKATE AREA AS SHOWN ON THE PLANS BELOW. THESE ELEMENTS, ENTITLED THE RIBBON, WHALE TAIL, AND WHALE TAIL RETURN, SHALL BE PROVIDED BY SPOHN RANCH INC. (SRI), WWW.SPOHNRANCH.COM http://www.spohnranch.com; 877 489-3539.

BESIDES SHIPPING AND HANDLING, SRI PROVIDES CERTIFIED INSTALLATION FOR THE ELEMENTS. THE CONTRACTOR SHALL PROVIDE ALL REMAINING SERVICES AND ITEMS, INCLUDING ALL FOOTINGS AND SURROUNDING CONCRETE PAD. A PRELIMINARY GEOTECHNICAL REPORT IS AVAILABLE FOR REVIEW, BUT IT IS ANTICIPATED THAT A FINAL REPORT WILL BE REQUIRED (CITY OF FALLS CHURCH TO PROVIDE). ANCHORING DETAILS AND SRI CONDITIONS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL WORK DIRECTLY WITH SRI FOR PRODUCT AND INSTALLATION INFORMATION AND REQUIREMENTS.





DETAIL # / PAGE MATERIAL KEY 1.1 STONE DUST TRAIL 2/2 1.2 ASPHALT TRAIL 3/2 1.3 CONCRETE 5/2 1.4 CONCRETE PAVERS SITE FURNISHINGS & ELEMENTS 2.1 BENCH 2.2 SKATE PARK BENCH 2.3 BICYCLE RACKS 2.4 TRASH & RECYCLING RECEPTACLES 6/15

RIBBON ANCHORING DETAIL

IN REINF. TIES 18" ON CENTER

VolleyCrest -07 - 1079 - 84 --Stotodole Art


FOOTSING 2500 PSI CONCRETE


RIBBON SKATE ELEMENT SIDE VIEW

6"X8" (1A1") WELDED WIRE MESH TOP, BOTTOM AND SIDES-#4 REINF, BAR TIED TO MESH 1" AWAY FROM OUTSIDE OF WALL FOOTING: 2500 PSI CONCRETE 3 #4 TOP, BOTTOM, I MIDDLE --42" MIN. TOP VIEW ANCHORING DETAIL HOTE.

1) PRECAST CONCRETE HAS INTECRAL FOR BLACK THAT 4" SI AR SIDE VIEW ANCHORING DETAIL ... NATIVE SOIL 95% COMPACTION 1/2" ALL THRED 3/6" STEEL PLATE Hacienda Heights, CA. 91745 tel/fax 626-330-2611 PLATE DETAIL

WHALE ANCHORING DETAIL SCALE: N/A








SKATE PARK BENCH SHALL BE HIGHLAND PRODUTS GROUP LLC MODEL 154-1210, FLAT CONCRETE BENCH S' LENGTH, OR APPROVED EQUAL. FINAS I SHALL BE FOUSHED SMOOTH COLOR SHALL MATCH SKATE FEATURES OR APPROVED SUBSTITUTION. WWW HERE A

BENCH DETAIL 6 SCALE: N/A



BICYCLE RACK DETAIL SCALE: N/A

BIKE RACK (TYP.) CONC. PAVING W/ 2' X 2' GRID SCORING (TYP.)

GROUND LEVEL

3" CLR

DETAIL A

CONCRETE

PLATE DETAILS

BKCYCLE BOLLARDS SHALL BE SHALL BE DERO BIKE RACK COMPANY, DERO HOOP RACK, GALVANIZED STEEL WITH POWDERCOAT LIGHT GRAY FINISH, OR APPROVED EQUAL. INSTALLATION SHALL BE EMBEDMENT MOUNT OR APPROVED SUBSTITUTION DEPORT OF A DERO BIKE RACK COMPANY 888-337-6729 www.dero.com

NOTE: FOR THE TWO BIKE RACKS IN ASPHALT-PAVED AREA NEAR SKATEBOARD AREA, PROVIDE DEEPER SLEEVES IN CONCRETE FOOTING WITH ASPHALT PAVING EXTENDING OVER CONCRETSE FOOTING UP TO BASE OF BIKE RACK.

GRADING PLAN

3 SCALE: 1" = 10'-0"



SIGNED AND SEALED FOR LAYOUT PLAN AND GRADING PLAN ONLY.

WEST END PARK **IMPROVEMENTS**

CITY OF FALLS CHURCH, VA

SKATE AREA




Chantilly, VA 20151-1679

T 703.449.6700 F 703.449.6714

DESIGN PHR+A	SURVEY PHR+A
DRAWN	DATE
SME	JUNE 17, 2009
CHECKED	SCALE
DHS	AS SHOWN
SHEET C413-14	FILE NO.
13 OF 21	15907-1-0

CITY PLAN # 2009040



WHALE RETURN ANCHORING DETAIL SCALE: N/A

SPOHNCRETE CONDITIONS

GENERAL PROJECT ASSUMPTIONS

- All written documents will be generated using Microsoft Word, Version 2004
- All written obcurrents will be generated using interest Excel Vertice 2004.

 Spohn Ranch, Inc. (hereafter, SRI) shell provide PDF less of the technical appetitications for items in their scope.

 SRI shell only be responsible for the skating erea, unless, specifically contracted otherwise.

RESPONSIBILITIES OF THE CLIENT-INFORMATION REQUIRED

- The Client shall provide all existing digital files to SRI accurately portraying boundaries of the selected site, existing grading, utilities, drainage, and site amenities in AutoCAD 2006 format or a first property of the selected site, existing grading, utilities, drainage, and site amenities in AutoCAD 2006 format or a first property. The Client is responsible for retaining the services of a Structural Engineer, Civil Engineer, Electrical Engineer, Architect, Surveyor, Geolechnical Engineer, or any other specially consultants that may be required for the project
- All drawings will be reviewed and stamped by engineer retained by the Client
- The Client shall provide SRI with a description of the process for approving reports, plans, specifications, and costs. The Client shall provide SRI with any specifications, details, or title blocks required by Client.
- The Client shall provide SRI with all available information for utilities including electrical, water, sewer, irrigation and gas prior to commencing work.

 The Client shall provide all existing plans for the site, including any improvements, grading, facilities, drainage inform
- and site survey in digital format (.dxf, .dwg, or .pdf)
 The Client shall provide SRI with complete contact information for all utility companies serving the site The utilities shall provide SRI with underground utility locations and easement information
- . The Client shall provide SRI with a current field survey locating all above- and below- ground utilities, appurtenances structures, and easements
 - If a current survey does not exist it shall be the responsibility of the Client to coordinate the on-site mapping and development of a survey
 - The survey shall be in digital format that can easily be used with AutoCAD software

- o The survey shall be in digital format that can easily be used with AutoCAD software
 The Client shall provide SRI with a current overall base map displaying the side's relief through contour (maximum 1-foot contour interval) and spot elevations, in digital format that can easily be used with AutoCAD software

 All existing hardscape and structure foundations shall be delineated with spot elevations
 The Client shall provide SRI with a current (less than 12 months old) Geotechnical Report prepared specifically for the project site, completed and sealed by a Geotechnical Engineer registered in the state where the project is located if the report is over 12 months old, the original firm issuing the report shall provide a letter certifying that the report is still valid and no updates are needed, dated within 30 days of receipt of the Geotechnical Report

 The Geotechnical Report shall include the following at a minimum—vicinity map of the project limits, plot plant serial showing location of borings, detailed description of the findings and recommendations, a detailed report of the laboratory tests performed, and an executive summenry staling general findings and recommendations
- of the laboratory tests performed, and an executive summery stating general findings and recommendation.

 All permits required, unless specifically included in SRI's proposal, are the responsibility of the Client.

 The Client is solely responsible for verifying and property zoning the skatepark site prior to the outset of the project.

 - The Client certifies that the site is properly zoned for the intended us
 - in the event that zoning or variances delay the project, the Client shall be solely responsible for any additional

DESCRIPTION DATE REVS'D REVS'D APRY'D DATE



WEST END PARK **IMPROVEMENTS**

CITY OF FALLS CHURCH, VA

SKATE AREA

- Prices do not include any sales or special taxes, any importation / exportation duties, freight forwarding, or customs
- The Client is solely responsible for informing SR of any such taxes or fees to which they are subject Preveiling wage is not included in the base price
- If required, please see the additional costs outlined in the proposal or request a revised proposal Bonding is not included in the base price
- If required, please see the additional costs outlined in the proposal or request a revised proposal

SITE ACCESS AND CONDITIONS

TAXES/ PREVAILING WAGE/ BONDING

- The installation proposal is based on driving tractor-trailers and cranes directly onto the site without obstruction of there is not paved, unobstructed access to the site, installation costs may increase due to additional equipment needs, time, and labor required, which will be submitted to the Client via change orders.
- The installation proposal is based on there being no fence and no overhead obstructions which would limit crane function Any site obstructions requiring additional equipment needs, time, or labor, may increase installation costs which will be submitted to the Client via change orders
- The installation proposal is based on there being restrooms at the site within 100 yards that are aveilable for use by SRI
 o If there are not, installation costs may increase which will be submitted to the Client via change orders
- The proposal is based on the Client providing all structural fill material required for the project delivered to the site, unless
- If the site proves unsuitable for regular slab-on-grade construction, the Client shall be responsible for any additional site preparation, engineering or construction costs, unless otherwise specified in the contract.
 The Client is responsible for any and all issues associated with the existence of hazardous materials at the site, including

- but not limited to any mitigation required and any legal monitoring.

 The proposal is based on the Client providing disposal and a for construction debrits, unless otherwise specified in the event that other entities affect the site conditions. The proposal the progress of the skatepark installation, the
- Client shall be responsible for any additional costs.

 The proposal is based on the Client providing all earthwork including grading, compaction, scarification, backfill, berming,
- Client shall provide site fencing and security for the duration of construction.
- Any costs associated with a breach in security (e.g. vandalism) shall be the responsibility of the Client
- Client shall provide a map showing roads and access routes marked in detail for the crane.
- Client shall provide protection of underground utilities in the area of the site

PAYMENT TERMS

- SRI standard payment terms are 40% upon contract / purchase order, 40% upon shipment of elements, and 20% within 10 days of completion of the installation, unless otherwise specified
- Payments not made according to terms will be considered delinquent, and a service charge will accuse at the rate of 1.5% per month
 - in the event of litigation by SRI or by a licensed collection agency to recover money due for goods, products or services provided by SRI, or to recover SRI's property, Client shall be responsible for any agency and attorney fees incurred, including any fees to enforce or collect any judgment entered

PROJECT SCHEDULING

- The signed contract from SRI will include a date commitment to our Clients as to the shipping and installation schedule for
- The proposal is based upon skatepark equipment shipping directly to the site to be immediately unloaded and installed by SRI factory installers
 - If other arrangements must be made, installation costs may increase due to additional equipment needs, time, and labor regulated, which will be submitted to the Client via change orders
- If the site is not ready for any reason when SRI is ready to ship the skatepark equipment, additional charges may accrue, including storage fees and additional handling fees
 - SRI may agree to store the equipment at its facility for up to 30 days, depending upon its other commitments. The payment schedule is still in effect as if the equipment was shipped according to the original date.

 - If SRI is unable to store the elements, we will arrange shipping to a secure location of the Client's choice Additional charges (including, but not limited to labor, equipment rental, travel, and transportation) will apply for
 - SRI to unload the equipment at this storage location, re-load it onto other trucks when the site is ready, transport it to the site, and off-load it for installation
- SRI is not responsible for theft or damage of any kind while the equipment is at this storage location
 Under no circumstances shall the Client's staff or a third party handle the elements
 SRI is happy to accommodate rush orders for our Clients, if our production schedule permits
- Scheduling details and rush charges will be discussed on a case-by-case basis with the Client There will be a minimum rush charge of 10% of the total contract price to accelerate the schedule by 1-2 weeks
- Some limitations will apply, such as minimum construction schedules, and our prior professional commitments
- Minimum construction time is 4 weeks from the notice to proceed, with the average project taking ~12 weeks

LIMITATION OF LIABILITY


- Any liability of SRI which relates to the sale, manufacture, delivery, resale, installation or use of any goods sold by or furnished by SRI, whether arising out of contract, negligence, strict tort, under any warranty or otherwise, shall be limited to SRI's choice of the following: the repair of the goods; the replacement of the goods; the cancellation of the contract, return of the goods in question to SRI, and SRI's refund of the purchase price in no event shall SRI's liability exceed the price of the specific goods upon which the liability is based in addition, SRI shall not, under any circumstances, be responsible for special, consequential, or incidental damages such as, but not limited to, damage to or loss of other property, loss of profit, revenue or reputation; loss of capital; loss of
- purchased or replaced goods; or claims for delays, back charges, or loss of use
- SRI reserves the right to makes any corrections as necessary to typographic errors


Patton Harris Rust & Associates,pc Engineers, Surveyors, Planners, Landscape Architects



14532 Lee Rood Chantilly, VA 20151-1679 T 703.449.6700 F 703.449.6714

DESIGN	SURVEY 200904
PHR+A	PHR+A
DRAWN SME	JUNE 17, 2009
CHECKED DHS	AS SHOWN
SHEET C413-14 14 OF 21	FILE NO. 15907-1-0








TRAIL BENCHES SHALL BE LANDSCAPEFORMS AUSTIN

6' LENGTH, WITH CENTER ARM REST, WITH IPE HARDWOOD SLATS OR APPROVED EQUAL, FRAME POWDER-COAT FINISH COLOR SHALL BE SILVER OR APPROVED SUBSTITUTION. WWW.LANDSCAPEFORMS.COM

TRAIL BENCH DETAIL 5 SCALE: N/A



BENCH PLAN (4B) SCALE: 1/4"=1'-0"



TRASH RECEPTACLES SHALL BE LANDSCAPEFORMS CHASE PARK MODEL, SIDE OPENING, SILVER POWDERCOAT FINISH, OR APPROVED EQUAL. MOUNTING OPTION: SURFACE MOUNT.



RECYCLING RECEPTACLES SHALL BE LANDSCAPEFORMS CHASE PARK MODEL 10" TOP OPENING, SILVER POWDERCOAT FINISH, OR APPROVED EQUAL


TRASH & RECYCLING RECEPTACLES

GATEWAY AND EAST ENTRANCE SIGN DESIGN-BUILD NARRATIVE:

A DESIGN-BUILD CONSTRUCTION SCENARIO WILL BE USED FOR BOTH THE GATEWAY STRUCTURE AND SIGNAGE LOCATED AT THE WEST BROAD STREET ENTRANCE TO THE PARK AS WELL AS THE EAST SIGN LOCATED AT THE W. & O. D. TRAIL ENTRANCE. THE DESIGN-DOVELOPMENT PLANS ARE PROVIDED HEREIN AND IDENTIFY SPECIFIC SITE CONSTRAINTS DUE TO EXISTING UTILITIES IN THE SURROUNDING THE STRUCTURE. ALL CLEARANCES SHOWN FROM THE UNDERGROUND LITILITIES AND THE STRUCTURE'S FOOTING ARE CONTINGENT UPON FINAL APPROVAL FROM STRUCTURE'S FOOTING ARE CONTINGENT UPON FINAL APPROVAL FROM THE UTILITY COMPANIES (DOMINION VIRGINIA POWER AND MCI).

CONTRACTOR SHALL WORK WITH A SIGN DESIGNER AND STRUCTURAL ENGINEER TO PREPARE SHOP DRAWINGS THAT CONFORM TO THE DESIGN MITENT AS CLOSELY AS POSSIBLE; HOWEVER, RECOMMENDATIONS FOR MODIFICATIONS IMPROVEMENTS WILL BE EVALUATED. A PRELIMINARY SOILS REPORT IS AVAILABLE FOR THE FOOTING DESIGN. THE CITY OF FALLS CHURCH AND THE LANDSCAPE ARCHITECT SHALL REVIEW AND APPROVE ALL SHOP DRAWINGS PRIOR TO PERMIT SUBMISSION


GATEWAY LARGE LETTERS SHALL BE GEMINI SIGN LETTERS, FABRICATED METAL LETTERS, 304 STAINLESS STEEL ALLOY, WITH A STAINLESS STEEL SATIN FINISH, FONT STYLE SHALL BE AERIAL BOLD, LETTERS TO INCLUDE AN ALUMINUM LEXAN BACK WITH A NATURAL SATIN FINISH, LETTERS SHALL BE BOTTOM MOUNT WITH TWO STUDS PER EACH STROKE OR APPROVED



SIGN /ARCH MATERIAL: STEEL WITH POWERCOAT BROWN, FINISH 4" x4" TUBE STEEL W/ CLOSED ENDS WEST END PARK 7" HT. LETTERS ATTACHED TO SIGN PANEL, SEE NOTE BELOW FOR SIGN LETTER DETAILS (TYP.) CITY OF FALLS CHURCH -6" PRECAST COLUMN NOTCH COLUMN FOR SIGN PANEL, COLOR TO MATCH WEST BROAD STREET GATEWAY SIGN. RECREATION & PARKS DIVISION LETTER SIZE (TYP.) SEE NOTE BEOW FOR DETAILS

EAST ENTRANCE SIGN LETTERS AND NUMBERS SHALL BE GEMINI SIGN LETTERS CAST ALUMINUM, NATURAL SATIN FINISH, FONT STYLE SHALL BE AERIAL BOLD. FLUSH MOUNT OR APPROVED SUBSTITUTION. WWW.GEMINISIGNLETTER.COM

EAST ENTRANCE SIGN ELEVATION



ELEVATION OF SMALL SIGN AT GATEWAY 8 SCALE: 1"=1'-0"

REVISION

2) SCALE: 1/2" = 1'-0"




WEST END PARK **IMPROVEMENTS**

CITY OF FALLS CHURCH, VA

GATEWAY AND SITE FURNISHINGS Patton Harris Rust & Associates,pc

14532 Lee Rood Chantilly, VA 20151-1679 T 703.449.6700

	CITY PLAN / 20090407
DESIGN PHR+A	SURVEY PHR+A
DRAWN SME	JUNE 17, 2009
CHECKED DHS	SCALE AS SHOWN
SHEET C415gate 15 OF 21	FILE NO. 15907-1-0



DATE MEUS'D REVIE'D APRIV'D DATE




IMPROVEMENTS


CITY OF FALLS CHURCH, VA



14532 Lee Road Chantilly, VA 20151-1679 T 703.449.6700 F 703.449.6714

	Q11 1 D41 1 20004 701		
DESIGN PHR+A	PHR+A DATE JUNE 17, 2009		
DRAWN SME			
CHECKED DHS	SCALE 1" == 8"		
SHEET C416LND 16 OF 21	FILE NO. 15907—1—0		





LEGEND

LIMITS OF AREA TO BE SODDED

EX. TREE TO BE PRESERVED FOR GENERAL MASSING IN RELATION TO PROPOSED LANDSCAPING. TREE DRIP LINES SHOWN WITHIN FORESTED AREAS ARE APPROXIMATE SINCE ACTUAL DRIP LINES ARE INDISTINGUISHABLE WITHIN THE OVERALL CANOPY.

REFER TO SHEETS 8 THROUGH 12 FOR TREE PRESERVATION INVENTORY & NOTES. SEE TREE PRESERVATION PLAN FOR EXACT LOCATION AND PROTECTION METHODS)



EX. TREE TO BE REMOVED



EXISTING TREES OUTSIDE OF LIMITS OF PROJECT AREA TO REMAIN



EXISTING SHRUBS OUTSIDE OF LIMITS OF PROJECT AREA TO REMAIN



PLANT SCHEDULE

		TREES	_ {					
Amila	2		AmLa	2	Amelanchier laevis	Allegheny Serviceberry	2" caliper	B&B
⊅nn erret	6		ChTh ·	6	Chamascypans thyoides	Atlantic Whitecedar	6'-7" height	848
Op _	4		∦ KOp	4	Fex opeca	American Holly	6'-7' height	848
xAt'F'	5		LATE.	5	Eex x attenueta 'Fosteri'	Foster's holly	1" cal/6'_ht	8&B
lu VI	6		§ JuVí	6	Juniperus virginiana	Eastern Redcedar	6'-7' height	B&B
An Gr	1		MarGr	1	Magnolia granditora	Southern magnolia	2" caliper	8&8
AaV i	3		MeVi	3	Magnolia virginiana	Sweetbay Magnotia	2" caliper	888
uFa .	2		QuFa	2	Quercus faicata	Southern Red Oak	2.5"-3" caliber	B&B
⊇uPh	2	•	QuPh	2	Quarcus phetios	William Oak	2.5"-3" caliper	8&8
ThOc-N	3		# ThOc-N	3	Thuis occidentalis "Nigra"	Dark Green American Arbonitae	6' height	B&B
ПАт	1		TiAm	1	Tilis americana	American Basswood	2.5"-3" caliper	8&B
	-	*				.,	210,0 0240	
NbGr	9	SHRUBS	AbGr	9				
ArMe-M					Abelia x grandišora	Glossy Abelia	18"-24" height	container
	14		ArMo M	. 14	Aronia melanocarpa "Morton"	Morton Chokeberry	18"-24" height	container
CoPe	32		CoPe	32	Comptonia peregrina	Sweetlern	2 gaffon container	0
CoSe	65		CoSe	65	Comus sericas	Redosier Dogwood	18"-24" height	container
oG#	26	. 1.	FoGe	26	Fothergilla gardenii	Dwarf fothergilla	18*-24*	container
GaBr	68		GaBr	68	Gaylussacia brachycera	Box Huckleberry	15"-18" height	container
HaVi	11		HaVi	11	Hammemells virginians	Common Witchhazel	33"-48" ht.	container
/Ve	13		IVe .	13	Fex verticitists	Common Winterberry	24"-36" ht.	container
KaAn	11	1	KaAn	11	Kelmia angustifolia	Sheep Laurel	15"-18" height	container
KaLa	11		Kale	11	Kalmia latifolia	Mountain Laurei	18"-24" height	container
LeFo	10		LeFo	10	Laucothoe fontanesiana	Drooping Leucothoe	15"-18" height	container
LiBe	3		LiBe	3	Lindera benzoin	Spicebush	18"-24"	container
MyPe	22		MyPe	22	Myrica pennsylvanica	Northern Bayberry	18"-24" height	container
PIFI	44		PiFI	44	Pleris toribunda	Mountain Pieris	15"-18" height	container
Pri.a-O	s		PrL	5	Prunus laurocetasus 'Otto Luyken'	Otto Luyken Laurel	18"-24" height	Container
RhMa	11		RhMa	11	Rhododendron maximum			
ViiDe	14		VIDe	26	Vibumum dentahim	Rosebay Rhododendron	18"-24" height	container
	0		ž vina	20	TRANSPORT CONTRACTOR	Arrowwood Viburnum	24"-36" ht.	container
	Ö	GROUNDCOVER	w.			** *		
ArUv	50		VUA §	50	Arctostaphylos uve-ursi	Common Bearberry	#1container	24" on center
EpPe'F'	284		EpPeF'	284	Epimedium x pemalchicum Frohnleinten'	Frohileiten Epimedium	#1_container	12"_on_center
GeSe-M	43		GeSe-M	43	Gelsimium sempervirens "Margarita"	Margarita Carolina Jesmine	1 gallion	Container
isFi	65		∳ hsFi	65	isotoma fuviatilis	Blue star cresper	#1_container	24"_on_center
LeBu	31		LeBu	31	Leiophyllum buxifotium	Box Sandmyrtie	2 gation	container
		PERENNIALS	- E					
As Tu	124		AsTu	124	Asclepies tuberosa	Buiterflyweed	#1 container	15"-18" on cente
CoVe-M	130		Cove-M	130	Corecpeis verticillate 'Moonbeam'	Moonbeam Coreopsis	1 galfon	18" on center
DrLu	132		Drt.u	132	Dryopteris tudoviciona	Marginal Wood Fem	3.5" containers	12"-15" spacing
EuPυ	72		EuPu	72	Eupetorium purpureum	Sweet Joe Pye Weed	#1 container	24° on center
3aPu	87		GePu	87	Gallardia puchella	Firewheel	#1 container	15" on center
1050 GS	58		HeSa-GS	58	Heuchers senguines 'Green Spice'	Green Spice Coral Bells	2 gañon	18" on center
4Sp-PM	297		HeSp-PM	297	Hemerocallis species 'Pardon Me'	Pardon Me Davillo	i gallon	18" on center
leSp-SC	243		HeSp-SC	243	Hemerocallis species Strewberry Candy	Strawberry Candy Daylilly	#SP4_container	18" on center
to'RS'	117		Hores	117	Hosta Royal Standard	Royal Standard Hosta	#1 container	24" on center
rCr	263	•	lrCr	283	iris cristate	Dwarf Crested His		
rVi	176		i ivi	176	iris virginica	Virginia lifs	#SP5_container	8"-8" on center
.iMa	115		Libita	115	Litiem michauxii		#1_container	24"_on_center
OC#	176					Carolina Lily	1 gallon	24" apacing
			LoCa	176	Lobella cardinalis	Cardinal Sower	#1 container	18" specing
SeSpT' SeTe-AJ	102 153		SeSoF	102	Sedum spurium Fuldeglut	Fuldgiut Stonecrop	#1 container	8" on center
36 (8-M)	193		SeTe-AJ.	153	Sedism telephium 'Autumn Joy'	Autumn Joy Sadum	1 gallon	18" on center
*	-	GRASSES						
AuC#	208		MuCa	208	Muhlenbergia capitaris	Pink Heir Grass	1 galion	container
PaVI	30	111	PaVi	136	Panicum virgatum	Switchgrass	3 galfon	container

THIS SHEET TO BE USED FOR LANDSCAPING PURPOSES ONLY



IMPROVEMENTS

CITY OF FALLS CHURCH, VA


LANDSCAPE PLAN AND PLANT SCHEDULE





14532 Lee Road Chantilly, VA 20151-1679 T 703.449.6700 F 703.449.6714

	CITY PLAN # 20090407		
DESIGN PHR+A	SURVEY PHR+A		
DRAWN	DATE		
SME	JUNE 17, 2009		
CHECKED	9CALE		
DHS	1" == 8'		
SHEET C418LND	FLE NO.		
18 OF 21	15907-1-0		



LANDSCAPE NOTES

SPECIFICATIONS FOR PLANTING City of Palls Church, VA - Urban Fore

- Constructor shall verify existing conditions and utility locations. The City Arborist prior to the
 planting must approve adjustments to locations of plant material due to field conditions. Any
 substitutions in plant material and sizes specified will not be accepted, unless approved by the
- 2. All plant meterial shall comform the <u>Augurices Standard for Numery</u>, latest edition, published by the American Numery and Landarage Association. All plants must be free from injury, insect influentions and disease. All plant meterial must be inspected by the City Arborist prior to planning. The Contractor shall place at least those (3) days prior to installations for impaction of the material
- 3. All plant material amet bear original acroory tags indicating the genus, species and if applicable
- 6. Test soil drainage before planning. Dig a lode as deep as your planning hole and fill with water. If water drains at a rate lost than one indo per hour, install drainage to carry water eway from the planning the beat, or norwing or mixing the planning take form construction.
- Examine soil for compaction before plasting, If soils are compacted in an area where a group of plasts are to be installed, incorporated several inclines of a combination of organic materials such as composed year water, finely starteded piece bank matter (apper/sea) or threeded, composed leaf match (seaf-grov) and fill to a depth of twelver ([2]) to sightmen ([3]) inches over the sealers area, bon not fill if plasting is within a tree preservation area. Apply the organic matter at a rate of one-quarter organic matter to three-quarters existing out.) Do not incorporate ansite road compaction will increase and drawings decreases. For single tree plastings, backfull plasting holes with unaspended roal. Increase the width of the syot of the plastings hole in any where soil has been desired. Do not incorporate organic road in the soil plasting holes.
- 6. Thee pits shall be a minimum of two (2) and a baif (1/2) times the width of the root ball and no deoper them the height of the root ball. On balled and towlaped trees, runnove pinning natls or rope lacing, then one sway the wrapping and then backfull. Romove the top 12° of the wire bashet. Romove the rope 12° of the wire bashet. Romove all repe, whether place or sylos, from transle. For constainer testiming, construct the constainer consideredy. Select trees grown in constainers with vertical rits or a copper-treatment on the interior wall. These constainer scotlinerions and treatments unstainers intering roots from the robots are circling amound the root ball exterior of considerer places (trees, skeubs or permeasisk) out through the roots and old in a few places. Constainer two with moliphic eleming roots will be rejected. Place struttle and parceasials at the same depth they were in the constainers. For here root percentisis place with the role even with the role of yor of the crown. Dig the hole which enough to allow the troots to apread out in the soil. Path the soil back into the hole over the roots and around the top of the plant.
- 7. A soil test shall be made and the results submitted to the City Arborist prior to the installation

For trees: A slow-release granular fertilizer shall be incorporated into the top foor (4) inches of backflß soil to provide sirrogen, or if a soil test indicated a need for phosphorus or potestism. Use no more that I B. Actual sitrogen per 1,000 ft. of pleasing hole surface. (Example - if using 18-6-12 wifts a 5' dismeter hole, incorporate U3 oz. per pleasing hole.)

For shrubs: A slow-redesse granular fertilizer shall be incorporated into the top four (4) inches of backfill soil to provide mitrogen, or if a soil test indicates a need for phosphorus or possesium. Use

For percentials, bulbs and annuals: A slow -release high phosphete fertilizer such as 7:40-6 or approved equal shall be incorporated into the top four (4) inches of the baolofili mix. Alternati separative open many constructions and are stylened by factor of the result in the contention to the contention of the c \$420 phosphorus acid shall be incorporated into the backfill mix.

- 8. When half of the backfill has been returned to the planting hole, water shall be applied to provide actifement and eliminate air pockets. The tree shall be thoroughly watered again after the remaining soil has been planted in the planting pit. A three (3) to four (4) inch date of soil shall be constructed again.
- 9. Two (2) to three (3) inched of mulch shall be piacod over the bree-planting pit, but shall be kept three (3) to four (4) suches away from the trusk of the tree or crowss of sharubs. Do not allow mulch to beach the trusks of trees or crowss of sharebs. Use mulch that is comparished with the type of plant used. Avoid mulch that has not been sitrogen composted, as the pit of the soil ordered datages as the mulch degrades. Pins bark match will not change the pit of the soil as it degrades. This is the best type of mulch for use with permansials. In mulching personishs, are as more than 1.2". For Meditoranson type of percentials, such as lavander, or fax peomies or iris, see no makeh at all.
- frees shall be planted at the height of the surrounding grade with root flares visible. Should soil twe been piled over the most flare during the digging process, this soil shall be removed so that the
- Any proxing must be done with the approval of the City Arborist. Pruning at the time of planting shall be done only to remove broken branches or double (or donziment) leaders.
- 12. Remove tags and labels from trees and shrubs to provest girdling branches and truste.
- 3. Stakes shall be used only in area of high intiffic or highly windy locations. A tree-staking diagra should be provided if staking in necessary. Stake for maximum of one year. Allow trees a slight amount of flox rather than holding them rigidly is place. Use gaying or attaching that worl dam the back. To prevent brack gridling, remove all gaying material after one year.
- 14. Use tree wrap only on this beried trees planted in spring or summer into hot or paved areas. In these immences use white wrap, attaching with out the use of wire, rope, rice or tape, and remove
- 15. Planting Season Planting shall be done only within the following dates:
- Decidators Trees March: 15 to May 30 or September 15 to December 15 (oaks and black gaze to be spring dag and plasted only).
 Bivergeton Trees March 1 to May 15 or September 15 to November 15.
- 6. All plant numerial abail be guaranteed by the Contractor for one year fiture the date of act be in good, healthy and flourishing condition. In the event that a plant dies or in the index City Arteriat, fails to flourish; the Contractor shall replace in accordance with the above to the contractor.
- 17. The Contractor shall be responsible for the materiorance of the plants during this one-year warrant period. This trainitesance shall include providing water on a weekly beais when central minfall is less than one indult a work. Dip integration appearers and water memory devotes one facilities were reserved devotes one facilities were reserved devotes one facilities were facilities when the contract Root bell's of trees should be slowly and thereughly costed at time of watering. Por planting beds. (i.e., seen, shrube and passensisis), water slowly and desply parting down 1*-2* of water in a 6-12 hour period. This should give a passension of 12-18* depth.

1.4 GERGERAL CONDITIONS

- A. The lendscape contractor shall provide all asserials, labor, and equipment required to comple all lendscape maintenance work as outlined in these SPECIFICTIONS for a one year period.
- A. The landscape contractor shall be familiar with the project premises and how the existing

1.2 Personnel

The contractor's professionally purietained personnel shall, at all tirsus, present a nest arrows The contractor's professionally unstrictured personnel shall, at all times, present a neet appearance, and all work that the personnel and confugue that the mention of which required the Celly public relations. The City and the contractor will such be promptly notified by the other of any comparison received from City resplayones, City readessor of City property creams: The contractor shall utilize compense of the city of the contractor shall utilize compense explayone in performing the work specified in this Agreement. At the request of the City's Recreation and Parks Division, the contractor shall triplace say incompenset, whichtigh, shusive or

The continuous is required and hereby agrees by accepting this contract, to pay all employees not less than the Faderal Ministrum Wage and to about by other requirements an established by the Congress of the Lieferd States in the Fair Labor Standards Act, as assented, and changed from time to time.

The contractor shall provide a statement that their firm is an Equal Opportunity employer.

Trained personnel using current, acceptable horizontural practices shall perform all landscape maintanance. The qualifications of personnel serving as threemen, perticible applicative and IPM season smooth be submitted shang with the high package. The qualifications of those key personnel will be a factor in the award of this contract. The forcesse masser remain on site all those when the crown is worthing. The forcesses mass the financia in the English beauguage.

- A. All operators of power equipment shall conform with OSHA regulations
- All work shall be performed in a manner, which maintains the original integrity of the lanchome dealers.
- All chemical applications shall be performed in accordance with current county, state, and federal laws, utiliting EFA registered materials and methods of application. These applications that like performed under the supervision of a licensed Cortifica applicance. Selection of chemicals shall be in accordance with the current Virginia Cooperative Entension Service Bulleties. The contractor shall perecity to the City what chemicals are being used as individual sites and be proposed to present information regarding the chemicals, if requested by the City
- A. All areas noted "Organic Gerdening (OG)" on the List of Sites attached (see Appendix) shall receive neither synthetic chemical posticides nor synthetic fertilizers.
- A. All areas noted "PPM" (integrated Post Management) on the List of Sitte attached (see Appendity) shall have regular sociatoring and tracking of pest populations as a central part of this program. Abstractive methods to broad spectrum posticide applications such as biological releases or aeloction of post resistant plant material will be used where practical. Selective

- A. During landscape maintenance operations, all eross shall be kept nost and close. Precaution shall be taken to avoid damage to existing structures, public or personal property. All work shall be performed in a self transact or the operators, the occupants and any podestriators.
- A. All fertilizers remaining on pewed surfaces must be removed at the coal of each day. Neither compost nor match shall be piled near storm drains. When compost must be temporarily secred in piles, atnew bales shall be used to prevent leakage of materials.
- . Upon completion of maintenance operations, all debris and waste material shall be cleaned up and removed from the site, unless provisions have been granted by the City for disposal or

The laudscape contractor shall scales every effort to maintain the health and growth of all plans material. The contractor shall not be responsible to gastrastee the plant material, except when the constactor has obviously been negligent in the performance of instines work as collised in these SPECEPICATIONS and caused learns to plant natural, higheston systems, ear. The contractor will be held responsible for the repair or replacement of damaged City property. Plant material or irrigation systems parts which are ofsamped to the cutes that they must be replaced, as determined by staff of the Romeston and Parks Division, shall be replaced within fourteen (14) catendar days under the City's supervision. In the overest plant material is damaged outside the appropriate planting season for a perflusive plant or plants, then (those) plant(s) shall be replaced at the beginning of the next planting season. The constancts whall provide the irrigation necessary for the establishment of the newly planted replacement materials.

1.4

The isodecape work performed by the contractor as described in this Agreement shall begin at the City's request. Each area swarded, once began, shall be for a continuous period through February 28, 2002, subject to the provisions of this Agreement.

The contractor may perform the work on weeksleys (Monday through Friday between the hours of 7:30 c.m. and 4:00 p.m. Special permission most be given, in advance, by the designated contact saff of Recreation and Furbs to allow work to be performed on the weekneds (Saturday and Sunday). In the ovent that work is performed on weekneds the hours of operation shall be 9:30 c.m. to 5:00

1.5 Equipment

The contractor is responsible for providing, maintaining and transporting all necessary equipment, and left for tax is, in connection with the program of sendance maintenance described in this Agreement. The contractor shall provide all tools and supplies somesery for performing the work required by this Agreement. No vehicular equipment (carrs, tracks, etc.) is allieved aff of paved serateses on City properties.

1.5 Communication with City Staff

The constructor shall be responsible for contacting the designated Recession and Parks staff person such Monday monatog with a schedule for that weak's proposed work plan. Adjustments to that echedules, due to weather or other problems see to be made by planus or fix. Each day that the constructor is working in the City, the foreasts for the cover shall consact the designated staff person

A list of work completed such day (to include work location and work performed) shall be provided

to the designated Recreation and Parks staff person at the end of each week

Copies of IPM scouting reports and recommended treatments shall be submitted as required to the designated Recreation and Parks staff person.

- Compost. Compost shall be "Lost-Gro' or approved equal. Compost meat be of a manurity and quality suitable for top-dressing soils in ornancental landscaped ernes. He pH most be within limits of plant belorance when withind as a top dressing. No particle shall exceed on-balf (1/2") distractor and so more than one percent (1%) shall be man-made materials.
- bluich shall be 'Virginia Pines' or approved equal pine bark mulch. No perticle shall be larger than it "dismoter. The tase of mulch shall be limited to 2" in depth and applied only as the existing mulch is cubitved into the deal of in renowed.
- C. Pesticides, fortilizers lime, etc., used in landscape maintenance shall be selected based on the most current information provided by the University of Maryland or Virginia Polynchesical Institute (VPI) and currently labeled by the EPA for its proposed use.

3.6 Maintenance of Landscaped Reds - Trees, strubs, percentials and other g

In early spring, soil tests shall be performed for each location designated for soil sesting on the List of Sites for Azossal Soil Testing (see Appendix 3). The tests shall determine soil sextone, pH, cotal calcium, pagancelum phosphorous, potassium, subble saits and percent organis-matter. Each sample to be submitted for testing shall be extracted from a composite sample representing a stinismum five core samples for each soil area. Samples shall be taken from a defined growing area with plants of similar growth ability, such a trees, shralls, hetmocous plants, and test. This procedure should be performed for each distinctively different growing area in the menaged landscope. Soil tests shall be conducted by the State agricultural soil testing laboratory or by a commercial agricultural laboratory.

Additional soil tests may be required to diagnose falling plant material.

All soil testing costs shall be borne by the contractor. The results of the soil tests, together with the recommendations for corrections of deficiencies, shall be submitted to the City.

B. Each soil test shall examine the following chemical and physical stributes. Any soil that falls within the indicated range of results shall be considered acceptable. Soil that falls outside of any of the adolested range may be amended, rectated and resubmitted for approval by the City.

- A. The purpose of fertilization and sull textural amendment is to prevent or correct nutrient deficiencies to improve tree, darub and herbacoous plant nuturial health. Specified areas shall be sell sampled and fertilized according to testing results.
- A. In the event that the soil test indicates the pH is beyond the acceptable range, use the methods indicated in Appendix 4 (see attached) to raise or lower the pH.

(To begin no later than March I said be completed not later than April I). Plant beds shall receive a general close up before composting and mulching. Clean up includes:

- A. Removal of leaves, trash, weeds and other debris
- Cutting back of herbaceous perennials left standing through winter, e.g. ornemental grasses, flowering perennials, etc.
- D. Turning of exleting mulch, removal of excessive mulch build-up in bods, and top dressing with compost specified under 2.0 (A) above, at the depth of one half (1/2) inch to one (1) such over personals beds and one (1) such over the roots of trees and shrubs.
- A. Where allowed (see Appendix for areas not designated "OG"), an application of a pre-emergent herbicide may be made if deceased occasery to help prevent weeds. Any herbicide seeked for a given area must be telerated by the materials in that but and be applied
- A. Edging of all beds at right angles to a depth of 2-3 inches except in the vicinity tree roots or of young trees. SPECIAL CARE shall be taken to not durange the roots of existing trees or to inhabit the spread of roots of nowly established trees.
- Application of pine bark amiles as specified under 2.0 (B) above to a depth of one (1) inch over percensials and other ground covers and two (2) inches over the roots of shrukes and trees. SPECIAL CARK is hall be since in the multi-long operation not over malch or over the bases of trees or crowns of shruke. All registed shall be kept 2-3 inches away from the treate of trees.

- A. After flowering, cut off spent flower heads.
- Allow leaves of defindits and hysolaths to remain for a minimum of six (6) weeks after flowers leave fields. Out off at base.
- Allow leaves of other builts to yellow naturally and then out off at the base.

- $\boldsymbol{A}.$ Cut all decideous perencials flux is to the ground during the spring clean-up
- A. After blooming, cut only the flowering stems. DO NOT REMOVE THE FOLIAGE
- A. If soil is bared in fall, following leaf removal, add mulch to 1" depth to percential beds

3.5 Ongoing Wood Control

- A. All bods shall be weeded on a continual basis throughout the growing season to maintain a nest
- A. Pro-exergens and post-exergens (foliar applied) hardscides shall be used where and when applicable and in accordance with the product's label. Hardscides shall not be used in area designated "OCF" on the Latel of Stee, use Apparation.
- A Hand worting shall also be performed as morted to have all beautiful and the of the control of

DATE MENS'D REWED APPRY'D DATE REVISION



WEST END PARK **IMPROVEMENTS**

CITY OF FALLS CHURCH, VA

LANDSCAPE NOTES AND DETAILS

Patton Harris Rust & Associates,pc Engineers. Surveyors. Planners. Landscape Architects. 14532 Lee Rood Chontilly, VA 20151-1679

T 703.449.6700

F 703.449,6714

STY PLAN # 2008040 PHR+A PHR+A JUNE 17, 2009 SMF CHECKED DHS AS SHOWN SHEET C419LND-DET 19 OF 21 15907-1-0

The landscape contractor shall be responsible for creating and maintaining site maps and site evaluation guides.

The landscape contractor will be responsible for performing soil tests as needed to identify nutricent imbalance for deficiencies causing plant material decline.

1) date
2) location of site
3) time in end time out of site
4) major problems and presence of beneficial insects observed and location on location map
5) method of quantification for particular past encountered. For insects on small trees, number per 25 leaves/needles, or number of p25 leaves/needles, or number of p25 leaves/needles, or number of p35 per p25 leaves should be counted. For the finding lanch, the number per branch, number of 50 pto per 25 leaves should be counted. For the finding lanch, the number per branch, number of branches infested or extent of trunk colonization should be determined.

For peats specific to Falls Church, the following are threshold indicators of population buildup that require the contractor to immediately provide the City recommendations for contract:

five of each on five leaves or plant deforming, leaves or plant deforming -all foliate; two per square inch -all trank; five por expance inch -Zulico scale: if three out of five trees of a species are infeated at a decasity of

two per square inch two po myregestation is off-color
-webstate observed
-three nymphal aktins occur per square toch
a with catico scale
-ms kill; bore grass

Adelgide:

Ants: presence
Black Vine: ten or score per plent on new Weevils growth
Beatles: three of five leaves examined are skelete
Caterpillars: three of five leaves examined are chewed

five lesions per leaf, one lesion on a petiole croziers (shepherd's bacterium crook) or

) control decisions 2) control techniques used

Recommendations for biological controls or outhural adaptations shall be provided to the City along with options for chemical treatments, as necessary. When beneficial organisms are present but chemical creatments must be used, matraile shaw will be set affect the beneficials shall be used; that is, Bl, horticultural apray oil, and safer insecticidal soap as appropriate and at the optional time for the particular material. Systematic chemicals shall be used only as a second choice. Sevin shall never be used to control aphido or spider mitre. In all cases, when chemical particulation must be used, they shall only be spot sprayed. The use of all controls must be approved by the City prior to treatment.

Plant pathogenic disease problems that can be resolved by pruning or removal of damaged plant parts will be performed as part of the contract, but only with approval and supervision of the designated Recreation and Parks staff person.

Applications of pesticides, horticultural oils, fungicidal scaps, etc. (any materials other than pre-emergent and post emergent iterfacides used in routine weed control) shall be made at an additional cost to the City. These additional applications must be pre-approved by the City. Spray operations will conver all tasserial up to a height of tworty-five feet (25°). Trees exceeding this height will be nerviced under a separate contract.

Control of diseases and insects shall be performed at an additional cost to the Cit

3.7 Trush removal

The landscape contractor shall remove trash from all shrub and groundcover beds with each visit.

All fallen leaves shall be removed from the bods and banked from the sites twice in November and once in December, Leaves removed from the sites will be dismosed of at the peacest City street carb (Leaf removal from tarf areas is specified under Section 4.0, below). These curb-side leaf piles shall be arranged in a manner that do not irangle vehicular or pedestrian traffic.

The project areas shall receive a general clean-up once during each of the winter mounts, i.e., December, January and Pebruary. Clean-up includes:

- Cleaning leaves and debris from costs and parking areas.
- of grounds and reporting any problems to the City/repair of winter mow removal

Tree/Shrub Fruning Rachaded

Unions otherwise directed, priming of all trees and shrubs will be performed by City crews or others under a separate contract with the City.

In the fall, the contractor will be responsible for two (2) leaf collections at specified locations in the City. These locations are noted in the Appendix. The leaf collection will consist of raiching or blowing all of the lowest to designated locations for pick, up by the Bravinonnetial Service Department. The leaf removal operations shall take piace between mid-November and mid-December, No leaves goall be regoved from wooded area or bare areas quade trees, Suff or Recercation and Parks will apport trees. Suff or Recercation and Parks will apport these. The leaf removal operations are also supported to the sufficient of the sufficie

The Contractor shall secure all pormits and licenses imposed by law and ordinance, pay all obseques and fees, and give all notices necessary and incidental to the doe and wheat protection of the work regarding the obstruction of streets and driveways, resistationing signals and open pessagenesys, and protecting the same where exposed. The Contractor will comply with all applicable redornal, State and Montingal laws, ordinances and regulations.

The Contractor shall not obligate the City to make any payments to senother party, nor make any promines or representations to snother party for, or in the behalf of, the City without prior written approval of the City Manager or his suthorized representatives. No word shall be done or any or trunk involved in such payments, promines or representations until much approval of the City Manager or his sundarized representative has been obtained.

The specifications and bid proposal submitted by the Contractor shall be incorporated herein and are

It is agreed that the Contractor must undorstand work priorities, maintenance methods and management techniques. Upon respons and/or necessity, as nuthorized City representative will accompany the Contractor to work areas to further clarify or describe maintenance methods and procedures. All work described in this Agreement shall be performed under the guidence of the Director of Recreation and Parks or his authorized representative and subject to his approval. The Contractor will consult with the City's representative regarding the densit, scheduling and performance of the innducape maintenance work and will provide weekly reports of work perform

The Contractor will arrange to knop sidewalks open for traffic whenever possible and will block portions of streets only when decemed accesses y to prused private property. Subject to prior approval by the Public Works Division, wenting signs and bertinedes that lib furnished and erosted by the Contractor when warranted. It is the Contractor's responsibility to renove all surplus measurial and debths from streets as work progresses in order that the public well have adequate use of the affected

5.6 Accident Prevention

The Contractor shall exercise procassion at all times for the protection of persons and property. Safety provisions of all applicable laws and ordinances shell be strictly observed. The Director of Recreation end Parks or his subordized representative may require the Contractor to discontinue hazardous work practices upon written notice. It is required that the Contractor keep the necessary guards and protective devices at locations where work is being performed to prevent injury to the public or demange to upolice or private property.

5.7 Payment for Services

In return for work performed by the Contractor, the City agrees to pay the Contractor mentally from March through February 23, 2002, as listed in the Appendix. The monthly bill will be a set amount bessed on the total price divided by the number of months of the contract. The first bill will be for March.

The Contractor will solvent monthly invoices and shall be paid according to the following:

The City shall check the sites to be maintained to ascertain whether the work was completed within the time schedule specified for each site. City records will be compared against the invoice from the vendor before payment is made. Payment will be made following receipt of the invoice for the previous mouth in which the Contractor completed the landscape maintenance and integrated post management work. The City retains the right to after areas

The Contractor agrees to furnish and maintain during the period of this Agreement, at its own cost, policies of insurance as follows:

- A. Covering the legal liability of the Commetor, and/or its subcontractors who may be engaged in the work, to pay claims for personal injuries to the Contractor's employe for the death; resulting theoretican noder applicable Workman's Compensation Law.

 B. Covering the legal liability of the Commetor to pay claims or damages for personal injuries (including death) on account of accidants to persons other than employees or
- agreements.

 The Contractor shall provide the City with a certificate issued by the insurance carrier or broker which evidences the coverage described above to the satisfaction of the City.

 The Contractor and all employees or agents of the Contractor assume all risk and danger
- incidental to the Contractor's obligations and operations provided in this Agreement. The Contractor agrees that seither the City nor any of its officials, compleyees, agents or representatives shall be liable for injuries (including doubl) arising out of the Contractor's ions and operations provided in this Agreement. The representatives shall be liable for injuries (including douth) arising out of the Contractor's obligations and oporations provided in this Agrooment. The Contractor and all employees or segarest of the Contractor do hereby forever release, remise and discharge the City of end from any and all manner of actions, ownes of action, claims and demands whosevers and howeover occurring for reasons of injuries (including death) to person or property, arising out of the Contractor's obligations and operations provided in this Agreemen

If the Contractor fails to perform the work in the manner specified by this Agreement, the City many, at its option, assess the Contractor for each day that the work is not performed. Hefore assessing inguished damages, the City will notify the Contractor of the problems and allow the Contractor twenty-four (24) hours to take corrective action. The assessment will be fifty dollars (530.00) per 43°, If after farriers written notion, the Contractor fails to take corrective action the CS9 many terminate this Agreement and either into an agreement writte notion; or perform the work itself. The cost of performing the work will be deducted from any amount does under the Psyment for Services achieved.

City Funding Prevision

The funding necessary to discharge the ongoing financial obligation of the City under this Agreement shall be finalised to each individual month, subject to the City Council approved budget appropriation. This Agreement does not obligate the turning power of the fill first and crostin of the City. In the event the City Council does not appropriate the finaling occasiony to find this Agreement is any future fiscal year budget, the financial obligation of the City shall cease at the end of the last fixed year budget appropriation.

PROJEC

The City reserves the right to causel any part of this contract.

The Constructor will post a Bid Bond of five percent (5%) of the bid price and a Performance Bond of one hundred percent (100%).

CITY OF FALLS CHURCH, VA

REFERENCES Phone:____ Business Name: Mailing Address:

HOURLY RATES OF MANPOWER & EQUIPMENT

Landscape Forenam
1PM Scosa
Spray Rig & Operator
Hand Spray & Operator
Landscape Worker
Landscape Worker
Are
Laborer (weeding &
pick-up of debris & litter)
Landscape Landscape

APPENDIX I

CONTRACTOR

Community Center (223 Liftle Faito Street)
City Hall Good Park Avames)
City Hall Parkindog Lot Islands
Cherry Hill Park Grounds
Cherry Hill Park Grounds
Cherry Hill Park Grounds
Old Fachioned Garden
Senior Conter (401 Groset Pala Street)
Library (228 North Virginia Avenne) Convery (1.20 Novem Avenue)

Convelor Contri-poster (unit-poster)

Noveth Maple Avenue between Park Ave. & W. Bread St.
Mist Park on Word Bread Street (between 169 & 200 blacks)

E. & W. Bread Street Streetscape corridors

Park Place Parking Let (behind Manustain Ascks)

Noveth Weshington Street Medikans and Streetscape planters

Millian Rouse (560 North Weshington Street)

Pendekton House (114 East Calumbia Street)

Madisses Park

I von Hense (259 East Brund Street)

Child Development Conster (111 North Cherry Street)

Prudy Park

Bases Brand and Tyson Drive Listmel

Rate Brund Street as Buriton Rand

Pt. Taylor at Ranoervell St. & E. Rroad St.

Roosevelt Benderard and Resonvell Street Island

Creassans Park at Foot Mile Ray

Creassans Park at Foot Mile Ray

Creassans Park of Foot Mile Ray Garden Court (mini-Creations Park at Creations Park Fire Department E Trolley Car Park Mt. Dealet Elemen

Mason High School/Middle School South Stee

Brend Street Streetstane Planters (both sides of street) from Havenck Rand to City Property Yard (Gordon Road) Reberts Park

Menticon Lone medien
Thomas Jefferson Elementary School
Rallina Strate right-of-way on thops (merth side of street)
Annucleus Rand and Cauchy Drive Island

TIDE

TOTAL COST TO CITY PER MONTH (Sections 1.8-3.9 and 5.8-5.9)

APPENDIX 2

Raking and Removal of Leaves Cost Per One Time (Section 4.8)

I. Lincole Park 2. Cherry Hill Park & Library \$

9. T.J. Elementary Streetscape Corridors on West & East Broad St.

11. 420 S. Maple St. (Aurera House) \$___ 10. Miller Boune (366 N. Washington St.)

13. Ives House (209 E. Broad St) 5____

TOTAL per removal (one time) \$____ Company Name Date

Typed Signature & Title Address

APPENDIX 3

List of Sites for Assured Soil Testing

Broad Street Streetscape Corridors (select five (5) locations) West End Park

wen and rara Caveller Trail Park (bods south side of stronm) Palls Church Library City Hall (East Wing area)

NOTE TO PERSON PREPARING SPECIFICATIONS: SHEET ON INCREASING AND DECERASING IS NOT IN THIS FILE AND MUST BE MANNUALLY ADDED TO SPEC PACKAGE!

7.9 Terf - Mowing, edging, trimming and other treatments

The contractor shall mow, trim, edge, rake and sweep the tarf great is certain specified areas in the manner specified in this section. The specific areas are listed in the Appendix, which is incorporated herein and shall be construed as part of this Agreement. Each area designated is to be completed before paging to the next one. Page City may add or drop areas and regulate the number of movings during the contract period.

7.1 Litter and Debris

Prior to each mowing, all trash, sticks and other unwanted debris shall be removed from all areas to be mowed. The contractor shall be responsible for disposal of collected little and debris. When fluished mowing, the contractor shall sweep and remove any dirt and greas clippings from curbs, sidewalks or streets adjoining the areas.

7.2 Mowing

Cool season grasses, including blue grass, tall feacus, percental ryegrass, etc., shall be maintained at a height of 2.9° to 3.9° in spring and fall. From Fuse through September, moving height shall be maintained at no less than 3°. To insare a high quality cut, all mover blades shall be sharpened no less than once a week during the moving season.

During the mowing season, all lines areas shall be moved every 5 to 10 days (unloss oriserwise noted on the List of Mowing? Frimming Locations, attached), or as weather conditions dictate. This is best determined by blade growth, since only 1/6 of the blade should be removed as any one cutting. Causion shall be used to avoid any thying others. The commence shall be especiable for expensable for demange done to petite or personal property as a rectif of debt is thrown by mowers. Safety glasses and our protection shall be worn during this operation.

Molching mowers shall be used. Loave the gram clippings unless the clippings are too long, in

The mowing operation includes trimming around all obstacles, removing excess grass of pipings and removing debris from walks, carbs and parting areas. The 'obstacles' shall include carbs, trees, bushos, phasting bods, willty poles, sign posts, fire hydrasts, utility boase and other objects as required to provide a uniform appearance. The trimming most be done on the name day as the mowing. Tomospag around trees shall projute hand trimming or using shaelds (such as flexible patter plants) to prevent designed to tree hard, from weed enters. Wend enters shall NOT come in contact with the back of trees.

Edging of all sidewalks, curbs and other paved areas shall be performed once every other moving. Debris from the edging operations shall be removed and the areas swept clean. Cautium shall be used to avoid any flying debris. Safety glasses and our protection shall be worn

4.4 Reporting of Damage

ny vandalism or storm damage to the areas, or to any of the troes, alzuba or objects locat e perk areas shall be reported to the City as soon as possible by the contractor. Also, any enage done by the contractor aball be reported to the City as quickly as possible.

4.5 The contractor will be responsible for cutting privately owned property following notification by the City. Those cuttings will be the result of the City having cited the owners for a "nall grass violation". The contractor is responsible for moving the site within seven (7) calendar days following notice by the City.

The contractor will be responsible for contacting the designated Recreation & Parks and person on Monday of each weck during the mowing season to propose the weekly nonwing season to propose the weekly nonwing season to propose the weekly nonwing schedule. The contractor may perform the work on weeklays (Monday funough Friday between the bours of 7.30 a.m. and 4.00 p., Special permission must be given by the designated Recreation and Parks staff contact to allow work to be performed on the weeken (Sei & San.) in the event that work is performed on the weekends, the bours of operation at be 9:30 a.m. to 5:00 p.m. School sites connect be moved between 7:30 a.m. and 3:00 p.m.

The contractor is responsible for providing, instinctiming and transporting all necessary equipment, and fuel for its use, in connection with the program of snowing and trinsming described in the Agreement. All tools and applies necessary for performing the work required by this Agreement will be provided by the contractor. Heavy originated (extensive right and the most is used. The contractor shall be responsible for repairing any run that are created by equipment that is inappropriately used for the soil conditions. No rehierable equipment (ears, truchs, etc.) is allowed off of paved surfaces on CVA properties.

LANDSCAPING TO BE PROVIDED IN THE DRAINAGE DITCH LOCATED ON NORTHERN VIRGINIA REGIONAL PARK AUTHORITY PROPERTY IS INTENDED TO ENHANCE INFILITATION AND POLLUTIANT REMOVAL OF STORM RUNOFF. LANDSCAPE INSTALLATION IN THIS AREA IS TO BE DEVELOPED PER AGREEMENT BETWEEN THE CITY OF FALLS CHURCH AND THE NORTHERN VIRGINIA REGIONAL PARK AUTHORITY (INVIRA). SEE SHEET 21 FOR A COPY OF THIS AGREEMENT. ALL WORK IN ASSOCIATION WITH RELIANDSCAPING OF THE DRAINAGE DITCH SHALL BE COMPUBLIED. DITCH SHALL BE COORDINATED WITH REPRESENTATIVES OF BOTH THE CITY OF FALLS

DRAINAGE DITCH LANDSCAPING NOTES:

1) EXISTING VEGETATION WITHIN THE DITCH AREA IS TO BE ERADICATED PRIOR TO INSTALLATION OF ANY NEW PLANT MATERIAL.

- 2) EXISTING VEGETATION SHOULD BE CUT BACK WITHIN 1' OF GROUND LEVEL PRIOR TO APPLICATION OF HERBICIDE. REMOVE ALL EXCESS PLANT MATERIA
- APPLY BROAD-SPECTRUM, GLYPHOSATE HERBICIDE PER MANUFACTURER'S RUCTIONS. SELECTION OF SPECIFIC OF HERBICIDE AND METHOD OF APPLICATION SHALL BE AS ACCEPTABLE TO THE CITY OF FALLS CHURCH AND NVRPA.
- ALLOW A MINIMUM OF SEVEN (7) DAYS AFTER APPLICATION OF HERBICIDE (OR MORE IF REQUIRED PER MANUFACTURER'S DIRECTIONS) PRIOR TO REMOVAL OF RESIDUAL VEGETATION AND TILLAGE. RESIDUAL PLANT MATERIAL SHALL ONLY BE REMOVED WHEN CONTRACTOR IS READY TO MIMEDIATELY PROCEED WITH INSTALLATION OF THE SLOPE STABILIZATION FABRICS SO THAT THE DISTURBED IS OPES OF THE DITCH DO NOT REMAIN EXPOSED. ALL RESIDUAL PLANT MATERIAL IS TO BE REMOVED FROM THE PROJECT SITE.
- ESTABLISH SOIL PH AND FERTILITY PRIOR TO LANDSCAPE INSTALLATION, ADD LIME AND FERTILIZER AS RECOMMENDED BY SOIL ANALYSIS. ALL INCORPORATING ACTIVITIES SHOULD BE DONE IN A MANNER THAT WILL LEAVE THE SOIL ROUGH, WHICH WILL IMMINIZE SOIL EROSION AND RAPID RUNOFF.
- INSTALL BIODEGRADABLE SLOPE STABILIZATION FABRIC ACROSS THE ENTIRE DITCH SECTION PER MANUFACTURER'S DIRECTIONS AND DETAIL SHOWN ON SHEET 19.
- LOCATE ALL PLANTINGS AS INDICATED ON DRAWINGS. IF OBSTRUCTIONS ARE ENCOUNTERED THAT ARE NOT SHOWN ON THE DRAWINGS, DO NOT PROCEED WITH PLANTING OPERATIONS UNTIL OWNER'S REPRESENTATIVE HAS SELECTED ALTERNATE
- CUT AN "X" IN THE SLOPE STABILIZATION BLANKET FOR EACH PLANT TO BE INSTALLED.
 CUT ONLY AS LARGE AS NEEDED FOR PLANT INSTALLATION. FOLD CORNERS OF EACH CUT UNDER STABILIZATION BLANKET UNTIL PLANT IS INSTALLED. AFTER PLANT IS INSTALLED, UNFOLD CORNERS AND TACK IN PLACE AT BASE OF PLANT.
- EXCAVATE CIRCULAR PLANT PITS WITH VERTICAL SIDES. PROVIDE PITS AT LEAST TWO TO THREE TIMES AS WIDE AS THE ROOT SYSTEM. DEPTH OF PIT SHALL BE NO GREATER THAN ROOT BALL DEPTH. SCARFFY BOTTOM OF THE PIT, REMOVE EXCESS EXCAVATED.
- 10) SET PLANT MATERIAL IN THE PLANTING PIT TO PROPER GRADE AND ALIGNMENT. SET PLANT MATERIAL NO LOWER THAN THE FINISH GRADE OR 7:3" ABOVE PINISHED GRADE. NO FILLING WALL BE PERMITTED AROUND TRUNKS OR STEMS. BACK FELT THE PIT WITH EXISTING SOIL OR APPROVED TOP BOIL MIX. FORM A RING OF SOIL AROUND THE EDGE OF EACH PLANTING PIT TO RETAIN WATER. SET ALL PLANTS PLUMB AND STRAIGHT. SET AT SUCH LEVEL THAT A NORMAL OR NATURAL RELATIONSHIP TO THE GROUND IF THE PLANT WITH THE GROUND SURFACE WILL BE ESTABLISHED, LOCATE THE PLANT IN THE CENTER OF THE PIT.
- OF THE PIT.

 AFTER PLANTS ARE SET, MUDDLE PLANTING SOIL MOTTURE AROUND BASES OF BALLS AND AFTER PLANTS ARE SET, MUDDLE PLANTING SOIL MOTTURE AROUND BASES OF BALLS. PLANTS SHALL BE HANDLED FROM THE BOTTOM OF THE BALL ONLY.
- 12) SPACE GROUND COVER PLANTS IN ACCORDANCE WITH INDICATED DIMENSIONS.
- 13) WATER PLANTS THOROUGHLY TO PULL SOILS AGAINST ROOT BALL AND SETTLE AIR POCKETS. ADDITIONAL SOIL MAY BE NEED, WATER AGAIN TO ENSURE COMPLETE.
- 14) DUE TO THE STEEPNESS OF THE EXISTING SLOPE, DO NOT APPLY MULCH AFTER
- 16) DUE TO THE STEEPINESS OF THE EXISTING SLOPE, PROVIDE WRAPPING, GUYING AND STACKING FOR LARGE SHRUBS. THE LANDSCAPE CONTRACTOR SHALL REMOVE STACING
- 18) REMOVE OR CUT BACK BROKEN, DAMAGED AND ASYMMETRICAL GROWTH OF NEW WOOD, UNLESS OTHERWISE DIRECTED, PRUNE EVERGREENS ONLY TO REMOVE BROKEN OR DAMAGED BRANCHES, EACH TREE AND SHRUB SHALL BE PRUNED IN ACCORDANCE WITH STANDARD HORTICULTURAL PRACTICE TO PRESERVE THE NATURAL, CHARACTER OF PLANT, PRUNING SHALL BE DONE WITH CLEAN, SHARP TOOLS.
- 17) UPON COMPLETION OF PLANT MATERIAL INSTALLATION, ANY DISTURBED AREAS BETWEEN THE NEW LANDSCAPING AND THE EXISTING ASPHALT TRAIL SHALL BE RE-SODOED AS INDICATED ON SHEET 8.

THIS SHEET FOR LANDSCAPING PURPOSES ONLY

NO. DATE HEVS'D REVIE'D APRIY'D DATE



WEST END PARK **IMPROVEMENTS**

CITY OF FALLS CHURCH, VA

LANDSCAPE NOTES AND DETAILS

14532 Lee Road

Patton Harris Rust & Associates,pc

Engineers. Surveyors. Planners. Landscape Architects.

Chantilly, VA 20151-1679 T 703,449,6700 F 703,449,6714

PHR+A PHR+A SME JUNE 17, 2009 AS SHOWN DHS SHEET C420LND-DET FILE NO. 15907-1-0 20 of **21**

CITY PLAN # 20090

DOMINION VIRGINIA POWER LICENSE AGREEMENT

TE 009041006

LICENSE AGREEMENT

THIS LICENSE AGREEMENT made on the ______ of October, 2009, by and between VIRGINIA ELECTRIC AND POWER COMPANY ("Licensor"), a Virginia impration, and CITY OF FALLS CHURCH a body, corporate and politic ("Licensee").

RECITALS

A. Licensor has previously acquired certain interests in land, by easement and In fee, in the City of Falls Church, Virginia, for the construction and operation of future and/or existing facilities for the transmission of electric power, said existing facilities currently known and identified by Licensor for its own purposes as Electric Transmission Lines 251 and 266 along the W&OD Trail - NRVPA Corridor. Such easements are hereinafter referred to as the "DVP Right-of-Way" or "Fee Property" and listed here as recorded in the Circuit Court of Fairfax County, Virginia:

WACD Trail - NRVPA Corridor (COR0525/5) tound in Deed Book 4910 Page 172 Easement retained in Deed Book 168, Page 516

Fee Property found in Deed 1444 Page 131

B. Licensee proposes to install and maintain a thirteen (13) foot high sign, an eight (8) host high sign, a six (6) foot wide concrete and asphalt trail, a culvert and plantings ("License Facilities") in the OVP Right-of-Way or Fee Property adjacent to West End Park near the northerly side of West Broad Street and west of Grove Avenue in the City of Falls Church, Virginia.

C. Licensor is willing to grant a license to the Licensee to utilize a portion of said DVP Right-of-Way and Fee Property for such purpose.

AGREEMENT

NOW, THEREFORE, Licensor and Licensee agree that, for and in consideration of the sum of Ten Dollars (\$10.00), the receipt and sufficiency of which is hereby acknowledge Licensor does hereby grant unto Licensee a License to occupy a portion of DVP Right-of-Way or Fee Property with Licensed Facilities as hereinafter defined, subject to the

- 1. The above Recitats are incorporated herein by reference.
- 2. The minimum distance required by OSHA shall be maintained between electrical conductors and any part of the encroachment or equipment used in the installation or maintenance of the encroachment. Sag of conductors varies with changes in operating and ambient temperatures; therefore, required clearances will be based upon maximum sag. The minimum clearance shall be governed by the clearance required for the 250 kV lims. See Exhibit '87.
- Licensor access to its facilities shall not be hampered at any time by the installation, use, maintenance or presence of the encroachment. Licensor shall not be liable for damage to the encroachment resulting from exercise of its easement rights.
- No portion of any house, garage, porch, deck, shed, barn, playhouse or any other type of structure whatsoever shall be permitted on the right-of-way.
- 6. Licensee shall restore any erosion or settling on the DVP Right-of-Way or Fee Property related to the installation or maintenance of the encoachment. Licensee shall comply with all state and local erosion and sedimentation control laws, and shall not adversely affect grade elevations and water drainage patterns.
- Licensee shall notify Licensor's Rights-of-Way Management Representative at (703) 375-5817 (Herndon Office) if any counterpoise (ground wire buried 18 to 24 inches deep) is damaged, cut, or severed, so necessary repairs can be made by Licensor the cost of which shall be reimbursed by the Licensee.
- Licensee shall be responsible for all associated costs for the repairs of Licenso facilities (including but not limited to structures, gays, anchors or counterpoise) damaged by Licensee, his employees, contractors or agents.
- 9. If the encroachment is determined to be unsafe by the Licensor at a future date, the unsafe condition shall be corrected or removed at Licensee's expense within forty-tive (45) days after written notification by Licensor. I find so corrected or removed by Licensee, the unsafe condition may be corrected or removed by the Licensor at Licensee's expense without liability by the Licensor for any resulting damage.
- 10. This Agreement is not a perpetual easement and in no way reduces the Licensor's rights under the easement(s) identified above. The Licensor may at any time exercise is easement rights in a way that conflicts or interferes with the encreachment described above. Upon notice from the Licensor, the Licensee will promptly modify, rearrange or remove the encreachment of enable the Licensor to exercise its easement rights without conflict or interference with the encreachment classes will be responsible to the cost of any such modification, rearrangement or removal. If Licensee lists to a modify, rearrange or remove the encoder memorial removal is the encreachment without liability for damage resulting therefrom, among or crows the encoderment without liability for damage resulting therefrom, and Licensee shall promptly reimburse the Licensor for the cost of such modification, rearrangement or removal.
- 11. Licensee shall begin physical installation of encreachment within one (1) year of the date of execution of this letter. If installation does not begin within that period, this Agreement shall become Invalid. A new letter of request addressing encreachment will be required before further consideration.
- 12. Licensee shall give at least five (5) days advance notice, except in emergencies, of any activities being performed within the DVP Right-of-Way or Fee Property to Licensor's Rights-of-Way Management Representative at (703) 375-9817 (Memdon Office) so that the Licensor, at its discretion, may have an inspector present while the work is in promotes, and Licensee oaves the codes of the inspector.

- Licensor will not be responsible for trees, shrubs or other vegetation planted within the DVP Right of-Way or Fee Property damaged as a result of its construction or maintenance work.
- 17. The planting of the trees, shrubs and other vegetation shall conform to the Licensor's guidelines. See earthist "O". Licensee will remove shrubs or trees exceeding the Licensor's intrinsitions, or otherwise deemed necessary by Licenseor within thing (30) days after notice by the Licensor. If not removed by Licensee within thing (30) days, Licenseo may remove each vegetation at Licensee's expense without liability to repetit the control of the co
- enhicies may be parked on DVP Right-drWay or Fee Property provided that:
 a. They do not exceed a height of 15 leet 6 inches.
 5 They are not house, office, or construction trailers.
 c. They do not carry explosives or flammable cargo.
 They do not carry explosives of flammable cargo.
 They are operative and the parking is of a transient nature.
 8. They stail have current inspection decass and shall not violate any local ordinances.
- 20. Should it be necessary to verify the final grade of the proposed cut/fill, then it will be the responsibility of Licensee to reinflurier Licensor for all actual costs. If the verification reveals that the cut/fill/grading was not done as approved, then Licensee is responsible for all costs involved with correcting the problem(s).
- Drainage ditches of such depth as to obstruct travel along or access to the DVP publicat. Was or Fee Property are not permitted trifless such ditches are provided with s installed and maintained at no cost to Licensor
- 22. Culverts shall be designed to support traffic crossings by heavy construction and maintenance equipment, and shall be capable of withstending AASHTO designated HS20-44 wheel loadings. Any culverts benefith access roads must be sized to accommodate water flows and prevent pooling in the DVP Right-of-Way or Fee
- 23. Licerisee may remove topsoli and grevel from portions of the DVP Right-of-Way or Fee Property not occupied by Licensor transmission facilities. In such cases Licensee must maintain a minimum island of undisturbor material with a tworty-five (25) loot radius on all sides of said facilities. The slope ratios, normally 3:1 or less, and transmission fine access lanes must be maintainised.
- 24. Licensee shall not assign or grant by license, permit or otherwise to any other party any rights, privileges or encreachments of any nature in, on, or with respect to the Licensed Facilities without the prior writers approved of Licensee. The obligations and requirements to which Licensee of Licensee. The deligations are provided to the control of the second of Licensee. The deligations and provided the prior of the control of Licensee, and no assignment or grant shall be brinding and the season of Licensee and on assignment or grant shall be acceptance of the obligations and requirements of Licensee under this Agreement. If Licensee is not the owner of the property on which the Licensee is not the owner of the property on which the Licensee is not the owner of the property on which the Licensee is not the owner of the property on which the Licensee is not the owner of the property on which the Licensee is not the owner of the property on which the Licensee is not the owner of the property on which the Licensee is not the owner of the property on which the Licensee is not the owner of the property on which the Licensee is not the owner of the property on which the Licensee is not the owner of the property on which the Licensee is not the owner of the property on which the Licensee is not the owner of the property on which the Licensee is not the owner of the property on which the Licensee is not the owner of the property on which the Licensee is not the owner of the property on the prop
- 25. All payments, notices, requests, demands and other communications required or permitted to be given hereunder shall be deemed to have been duly given if in writing and delivered personally, or mailed first class, postage prepaid, registered or certified

City of Falls Church 223 Little Falls Street

Falls Church, VA. 22046 Attention: Mr. Howard Herman

Dominion Virginia Power 701 East Cary Street, 12th Floor [23219-3927] P.O. Box 2666

P.O. Box 2000 Richmond Virginia, 23261 Attention: Electric Transmission Right-of-Way Management

In the case of any change of such mailing address, the party so changing a mailing address shall give notice thereof to the other party in the manner herein above provided. In the absence of any such notice, notice mailed in accordance with the foregoing section shall be deemed sufficiently given and served for all purposes.

- 26. Licensor shall not be responsible or liable for injuries (including death) or damage to property when such injuries (including death) are caused by or result from Licensee's use of the Licenseed Premises under the terms of this Licensee Agreement and are not solely due to the negligence of Licensor. Licensee shall require in all contracts with so contractors; that such contractors (in the contractor) and are not solely due to the negligence of Licensee of the contract of the contractors; that such contractors; that contractors; the contractors; that contractors; the contractors; that contractors; the contractors; that contractors; the co contractor(s) on Libonaed Premises. Such indemnification sisté also include the cost of defense, including altorney tesse and expert withouses feets. Licenses shall also requirs in all contracts with if contractor(s) that such contractor(s) must have insurance coverage for such indemnification, issient jucensor as an additional insured, in an emount of the greater of (a) the contractor's footal existing labelity coverage (including untrelia policies) or (i) Two Million and 90/10 Dollars (25,000,000,000, Licensee shall obtain from its contractor(s) is certificate of insurance demonstrating such insurance coverage and eldere a true and accurate copy of the certificate of insurance to Licensed Premises. Such insurance policies a their contractor(s) for the Licensed Premises. Such insurance policies a their feet of compellation for ten Licensed Premises. Such insurance policies shall also contain a requirement or te (10) days written notice to Licenser before any effective date of cancellation. No contractor(s) shall perform work on the Licensed Premises without full compliance with the terms of this paragraph.
- 27. This Agreement constitutes the entire agreement between the parties hereto with respect to the subject matter hered and supersodes all prior and contemporaneous negotiations, covenants, representations, agreements, and understandings of the parties hereto relating to the subject matter hereof.
- 28. The failure of any party at any time or times to require performance of any provisions hereof shall in no manner affect the right at a later time to enforce the same. No walve by any party of any condition, or of any breach of any term, covenant or representation contained in this Agreement, in any one or more instances, shall be deemed to be, or contained as, a further or continuing walver of any such condition or breach or a walver of any other term, covenant.
- 29. In exercising the rights granted by, and undertaking activity pursuant to, this Agreement, Licensee shall act in accordance with the laws of the Commonwealth Virginia and any other governmental body, state or federal having jurisdiction over

PROJECT

30. Should any one or more of the terms, provisions, covenants or conditions of this Agreement be held to be vold, invalid, liegal or unentroneable in any respect, the same shall not affect any other term, provisions, covenant or condition contained hereis.

IN WITNESS WHEREOF, the parties hereto have caused this License reement to be executed on their behalf by their duly authorized representative as of the date first above written

VIRGINIA ELECTRIC AND POWER COMPANY

Charles D. Hardy Manager : Transmission Right-of-Way

COMMONWEALTH OF VIRGINIA

CITY/COUNTY OF ____ Commonwealth of Virginia at large, do hereby certify that Charles D. Hardy, whose name is signed to the foregoing document on behalf of Virginia Electric and Power Company, appeared before me in the jurisdiction aforesaid and personally acknowledged the foregoing License Agreement.

GIVEN under my hand and seal this _____ day of October, 2009

CITY OF FALLS CHURCH

Howard Herman Department of Community Services – General Manager

CITY/COUNTY OF ____

...., the undersigned Notary Public in and for the Commonwealth of Virginia at large, do hereby certify that Howard Herman, whose name is signed to the foregoing document on behalf of City of Falls Church, personally appeared before me in the jurisdiction aforesaid acknowledged the foregoing License Agreement. GIVEN under my hand and seal this _____ day of October, 2009.

DOMINION VIRGINIA POWER LETTER OF PERMISSION

Dentistan Virginia flores 76: For Cary Street, Rickmond, VA 23215 Mailing Address RO, Bot 20666 Rickmond, VA 23261

November 9, 2009 Ms. Suzanne M. Corellessa Planning Director and General Manager City of Falls Church Harry E, Wells Building

Be: West End Park, Falls Church, VA Site Plan

Virginia Electric and Power Company is the owner of a parcel of land located between West Ford Park and the Washington and Old Dominion Trail. We have reviewed the proposed site plan and found the improvements shown on our land to be acceptable to us. Consequently, we will enter into a License Agreement with the City of Palls Church agreeing to the impro essements and fee parcel per the conditions and exhibits incorporated into that agreement.

VIRGINIA RESCURIC and POWER COMPANY

Chal A Has My Charles D. Hardy Manager Riectric Transmission Right-of-Way

Monard Henrico, City of Palls Church David Steigles, PHR+A Gery Doresta, St. Rights-of-Way Management Repres

VERIZON CONSENT AGREEMENT

November 6, 2009



Patton Harris Rust & Associates Attention: David H. Steigler, CLA, AICP Attention: David H. Steigler, C.L.A, AICP Director of Land Planning and Landscape Archite 14532 Lee Road Chantilly, Virginia 20151

RE: No Conflict Letter for West End Park, City of Fails Church; PHR+A F-15907-1-9

Per your request, Verizon has visited the West End Park, City of Falls Church project site and researched our records to identify Verizon Virginis, inc. facilities within the project boundaries. We have also reviewed your pre-final idealing plans. There is no conflict at this time.

- Verizon will still be able to access the identified manhole even though tree clearing is

- Verizon will still be able to access the identified materials event introduction encessary.

 Caution needs to be exercised with new tree plantings over the Verizon encased ductors due to the possibility of future damage to our structure.

 Since Verizon has an essement in this area, we have the right to remove any trees within the Verizon easement in order to maintain our structure.

 Verizon agrees with the need to perform test holes in the area where the new water structure is being placed across the Verizon due bank. A minimum of I clearance is required for future maintenance and to avoid any damage to the Verizon duct bank during construction. However, I avoid costly relocations Verizon will give strong consideration to modifying these requirements for this project.

If there are further concerns about this matter contact me on 703-390-3415 or via e-mail reginald.Llawson@verizon.com



NORTHERN VIRGINIA REGIONAL PARK AUTHORITY LETTER OF PERMISSION



Howard Herman
Recreation & Parks Division Director
City of Falls Church
223 Little Falls Street
Falls Church, VA 22046

RE: Permission for Landscaping and Connector Trail on the W&OD Railroad Regional Park at West End Park

NOV 1 2 7809

Dear Mr. Herman:

At your request, the Northern Virginia Regional Park Authority ("Authority") hereby grants permission ("Permis") to the City of Falls Church ("City") to construct, install, and maintain a connector that and landacapsing (cellotricity the "improvements") on the WCOD Rainton Regional Park ("W &OD Tail" or "Property"). The improvements are down on the plans prepared by Patton Harris Russ & Associates sittle "West Eas Fall Improvements," short strongs: 1.3 deed June 17, 2009 and revised through November 12, 2009, bershy incorporated Leibhids A. The Permit is subject to the following conditions.

- The City shall keep the W&OD Trail open, safe, and continuous all times during outstruction. Necessary safety prescutions shall be employed to protect rail users, including warring signs, flagmen and safety finening as appropriate. The limits of construction areas shall be separated from teal users by safety fineing. The City shall place signs on the Property warring trail users of construction about.
- 7. The Circ shall notify the Authority at least 48 hours in advance of construction work of
- 3. The connector trail within the 100-foot wide Property shall have a minimum 2-inch thick asplait surface after compaction and shall be underlain by compacted 6 inches of 21-A greed. This sub-base shall have a minimum 95% compaction. Additional sub-base material may be required over soft sub-grade. The buttom of the execution shall be compacted with a pline tamper, (unpring) jack or approved alternative prior to graved and suphish fluencemen.
- t. The shoulder of the connector trail shall be backfilled with 21-A stone to a depth of 2 inches by 1 foot wide and backfilled with imported topsed and seeded in accordance with Authoris.
- The connector trail shall have a maximum 2% cross slope and a maximum 5% running slope within the Property.
- 6. The presence trail shall intersect the W&OO Trail with straight edges (without flaring).
- The City shall ensure that the improvements and grading do not cause seros on the Property to hold water. The City shall be responsible for any erosion or devinage problems, which may occur as a result of the City's use of the Property, and shall restore any eroded areas until stabilized.
- 9. Vehicles, inois, equipment and materials shall be removed from the Property at the end of each workday said shall not be stored or stockpiled on the Property at any time. All debris end materials left over from construction, installation, and maintenance shall be retrained. No excavation shall be left open oversight.


- Access to the work area shall be from the City's property, and not along the W&OD passes trail. Construction equipment on the Property shall be approved by the Authority prior to construction. Personnel vehicles shall not be parked on the Property at any time.
- 11. The City shall promptly restore distarbed construction areas and adjacout areas to their original or better condition in compliance with conspactions, seeding, replanting and other applicable standards used by the Authority. The Authority may restore any areas in case of neglect by the City. The City shall pay the cost of each restoration, including the cost of seeding the City.
- The City shall maintain the commerce trial and landscape improvements installed on the Authority's property under this Permit.
- 13. As Dominion Vinginia Power holds certain rights over and on the property, the City must obtain its written permission for the connector trail and landscaping and provide a copy to the Authority prior to work on the Property.
- 15. The City shall provide all contractors on the project with a copy of this Permit and shall ensure that all construction personnel abide by the provisions contained herein. All contractors shall have a copy of this Permit on site.
- Connector trail compliance with the Americans With Disabilities Act shall be the responsibility of the City.
- 17 The City shall take adequate precautions to insure the safety of the general public as well as the City's and Authority's employees, to printed property, and to assure safe operation by the City's employees, against and absocurations. Whenever the City's activities create a serious leazest to public safety or welfare, the City shall take all reasonable actions immediately to absor the hazard. Authority shall have be right to direct the City to that any activity on the Property for noncompliance with the provisions of this Permit or when Authority believes it to be necessary to pretent the public's welfare on safety, until sack deficiencies or violentians are corrected. The City shall comply with any lawful directive given by Authority staff.
- 18. Construction of the improvements shall be completed within two years of the date of this Permit. This Permit shall remain in effect until the Authority cancels the Permit.
- condition. The Authority makes no representation or warranties, express or implied, concerning the condition of its property and shall have no responsibility for repairs and maintenance during the term of this Permit.
- in accordance with Article 38-29(d)(4) of the City's Code, the Authority, as owner of the Property, has no objection to joining the site plan shown on Exhibit A; however, it shall have no obligation in fulfilling the site plan requirements.

Please signify your acceptance of these conditions by signing both copies of this letter and



ACCEPTED:

DATE REVS'D REVW'D APRV'D DATI DESCRIPTION



WEST END PARK **IMPROVEMENTS**

CITY OF FALLS CHURCH, VA

CONSENT AGREEMENTS AND EXHIBITS

Engineers. Surveyors. Planners. Landscape Architects.

14532 Lee Road Chantilly, VA 20151-1679 T 703.449.6700 F 703.449.6714

Patton Harris Rust & Associates,pc

DESIGN SURVE N/A DRAWN JUNE 17, 2009 CHECKED SCALE N/A DHS SHEET C421UTL-AGR FILE NO 15907-1-0 21 OF 21